



CHALMERS
UNIVERSITY OF TECHNOLOGY

Imaging the water snowline in a protostellar envelope with (HCO⁺)-C-13

Downloaded from: <https://research.chalmers.se>, 2026-04-03 14:58 UTC

Citation for the original published paper (version of record):

van 't Hoff, M., Persson, M., Harsono, D. et al (2018). Imaging the water snowline in a protostellar envelope with (HCO⁺)-C-13. *Astronomy and Astrophysics*, 613.
<http://dx.doi.org/10.1051/0004-6361/201731656>

N.B. When citing this work, cite the original published paper.

Imaging the water snowline in a protostellar envelope with H^{13}CO^+ ★,★★

Merel L. R. van 't Hoff¹, Magnus V. Persson², Daniel Harsono¹, Vianney Taquet^{1,3}, Jes K. Jørgensen⁴,
Ruud Visser⁵, Edwin A. Bergin⁶, and Ewine F. van Dishoeck^{1,7}

¹ Leiden Observatory, Leiden University, PO Box 9513, 2300 RA Leiden, The Netherlands
e-mail: vthoff@strw.leidenuniv.nl

² Department of Space, Earth and Environment, Chalmers University of Technology, Onsala Space Observatory, 439 92 Onsala, Sweden

³ INAF, Osservatorio Astrofisico di Arcetri, Largo E. Fermi 5, 50125 Firenze, Italy

⁴ Centre for Star and Planet Formation, Niels Bohr Institute & Natural History Museum of Denmark, University of Copenhagen, Øster Voldgade 5–7, 1350 Copenhagen K, Denmark

⁵ European Southern Observatory, Karl-Schwarzschild-Str. 2, 85748 Garching, Germany

⁶ Department of Astronomy, University of Michigan, 1085 S. University Ave., Ann Arbor, MI 48109-1107, USA

⁷ Max-Planck-Institut für Extraterrestrische Physik, Giessenbachstrasse 1, 85748 Garching, Germany

Received 27 July 2017 / Accepted 3 January 2018

ABSTRACT

Context. Snowlines are key ingredients for planet formation. Providing observational constraints on the locations of the major snowlines is therefore crucial for fully connecting planet compositions to their formation mechanism. Unfortunately, the most important snowline, that of water, is very difficult to observe directly in protoplanetary disks because of the close proximity of this snowline to the central star.

Aims. Based on chemical considerations, HCO^+ is predicted to be a good chemical tracer of the water snowline because it is particularly abundant in dense clouds when water is frozen out. This work aims to map the optically thin isotopolog H^{13}CO^+ toward the envelope of the low-mass protostar NGC 1333-IRAS2A, where the snowline is at a greater distance from the star than in disks. Comparison with previous observations of H_2^{18}O show whether H^{13}CO^+ is indeed a good tracer of the water snowline.

Methods. NGC 1333-IRAS2A was observed using the Northern Extended Millimeter Array (NOEMA) at $\sim 0.9''$ resolution, targeting the H^{13}CO^+ $J = 3 - 2$ transition at 260.255 GHz. The integrated emission profile was analyzed using 1D radiative transfer modeling of a spherical envelope with a parametrized abundance profile for H^{13}CO^+ . This profile was validated with a full chemical model.

Results. The H^{13}CO^+ emission peaks $\sim 2''$ northeast of the continuum peak, whereas H_2^{18}O shows compact emission on source. Quantitative modeling shows that a decrease in H^{13}CO^+ abundance by at least a factor of six is needed in the inner ~ 360 AU to reproduce the observed emission profile. Chemical modeling indeed predicts a steep increase in HCO^+ just outside the water snowline; the 50% decrease in gaseous H_2O at the snowline is not enough to allow HCO^+ to be abundant. This places the water snowline at 225 AU, further away from the star than expected based on the 1D envelope temperature structure for NGC 1333-IRAS2A. In contrast, DCO^+ observations show that the CO snowline is at the expected location, making an outburst scenario unlikely.

Conclusions. The spatial anticorrelation of H^{13}CO^+ and H_2^{18}O emission provide proof of concept that H^{13}CO^+ can be used as a tracer of the water snowline.

Key words. ISM: individual objects: NGC 1333-IRAS2A – ISM: molecules – astrochemistry – stars: protostars – submillimeter: planetary systems

1. Introduction

Water is probably the molecule that appeals most to our imagination, as it is essential for life as we know it. In star-forming regions, water plays an important role as a coolant of warm gas, a dominant carrier of oxygen, and a major constituent of icy grain mantles deep inside a planet-forming disk (see, e.g., Melnick 2009; Bergin & van Dishoeck 2012; van Dishoeck et al. 2013, for reviews). The transition from water being frozen

out onto dust grains to being predominantly present in the gas phase occurs at the water snowline: the midplane radius at which 50% of the water is in the gas phase and 50% is in ice. Since the selective freeze-out of the major oxygen carrier alters the elemental C/O ratio in both gas and ice, the bulk chemical composition of planets depends on their formation location with respect to the freeze-out radius of water (e.g., Öberg et al. 2011; Madhusudhan et al. 2014; Ali-Dib et al. 2014; Ali-Dib 2017; Walsh et al. 2015; Mordasini et al. 2016; Eistrup et al. 2016; Booth et al. 2017). In addition, planetesimal formation is thought to be significantly enhanced in this region (e.g., Stevenson & Lunine 1988; Schoonenberg & Ormel 2017). The exact location and time evolution of the water snowline in protostellar systems is thus a crucial ingredient in planet formation.

* The NOEMA data are only available at the CDS via anonymous ftp to cdsarc.u-strasbg.fr (130.79.128.5) or via <http://cdsarc.u-strasbg.fr/viz-bin/qcat?J/A+A/613/A29>


** Based on observations carried out with the IRAM NOEMA interferometer. IRAM is supported by INSU/CNRS (France), MPG (Germany), and IGN (Spain).

Unfortunately, the water snowline is very hard to observe directly in protoplanetary disks. Because of the large binding energy of H₂O, the transition from ice to gas happens a few AU from the young star where the midplane temperature exceeds ~100–200 K (depending on the vapor pressure). For the nearest star-forming regions, this would already require angular resolutions of $\leq 0''.01$. Emission originating from cold water ($E_{\text{up}} < 100$ K) has been detected in the disk around TW Hya with the *Herschel* Space Observatory (Hogerheijde et al. 2011; Zhang et al. 2013), but the large *Herschel* beam (10–45'') could not spatially resolve the snowline. Furthermore, the only thermal water lines that can be observed from the ground (except for the H₂O line at 183 GHz) are lines from the less abundant isotopolog H₂¹⁸O. As such, even ALMA will have great difficulty locating the water snowline in protoplanetary disks.

An alternative approach is to use chemical imaging, as has been carried out for the CO snowline. Because CO is highly volatile, its snowline is located tens of AU from the central star (around ~20 K; see, e.g., Burke & Brown 2010). Although this is far enough to be spatially resolved with ALMA, locating it directly remains difficult; since CO line emission is generally optically thick, it does not reveal the cold disk midplane. Reactions with gaseous CO are the main destruction route for N₂H⁺, therefore N₂H⁺ is expected to be abundant only when CO is frozen out. Taking simple chemical considerations into account, an upper limit for the CO snowline location can therefore be derived from N₂H⁺ emission (Aikawa et al. 2015; van 't Hoff et al. 2017), as has been performed for the disks around TW Hya and HD 163296 (Qi et al. 2013, 2015), and several protostellar envelopes (Jørgensen 2004; Anderl et al. 2016).

For young protostars, the emission of complex organic molecules (COMs) has been used as tracer of the inner region that is warm enough to sublimate water ice, the so-called hot core, because these species are expected to be trapped in water ice. However, the exact binding energy, and thus spatial extent, differs for different molecules. Compact COM emission has been detected toward NGC 1333-IRAS2A (hereafter IRAS2A) extending between ~0''.4 and ~1''.0 (e.g., Jørgensen et al. 2005; Maret et al. 2014; Maury et al. 2014), similar to the size (~0''.8) of the H₂¹⁸O emission (Persson et al. 2012). The exact relationship between COMs and the water snowline remains unclear, however. For example, the extent of methanol emission in IRAS2A is half the size of the H₂¹⁸O emission (Maret et al. 2014), while it is twice the size in NGC 1333-IRAS4A (Anderl et al. 2016). In addition, Persson et al. (2012) concluded that C₂H₅CN is likely not related to sublimation of water ice. Since the detection of COMs is very difficult in mature protoplanetary disks, where only methyl cyanide and methanol have been observed so far (Öberg et al. 2015; Walsh et al. 2016), COMs are not suited as tracers of the water snowline in these systems.

The best candidate to chemically trace the water snowline is HCO⁺ because its most abundant destroyer in warm dense gas is gaseous H₂O, that is,



A strong decline in HCO⁺ is thus expected when H₂O desorbs off the dust grains (Phillips et al. 1992; Bergin et al. 1998). Atacama Large Millimeter/submillimeter Array (ALMA) observations of the optically thin isotopolog H¹³CO⁺ toward the Class 0 protostar IRAS 15398–3359 indeed revealed ring-shaped

emission (Jørgensen et al. 2013). The spatial distribution is consistent with destruction by water in the innermost region, but the inner radius of the H¹³CO⁺ emission is further out than expected. This can be explained if the temperature has recently been higher, that is, if the source has undergone a luminosity outburst. Follow-up observations by Bjerkeli et al. (2016) did not detect the H₂¹⁸O 4₁₄ – 3₂₁ high excitation transition ($E_{\text{up}} = 322$ K). However, an HDO transition with lower upper level energy ($E_{\text{up}} = 22$ K) was clearly detected. Although HDO emission is also present in the outflow lobes, the observations are consistent with the H₂O-HCO⁺ anticorrelation scenario.

Protostellar envelopes are good targets to test the H¹³CO⁺-H₂¹⁸O anticorrelation. Because of higher luminosity (due to higher accretion rates) and lower vapor pressure, the snowline is located further away from the star than in protoplanetary disks (10 s–100 AU instead of a few AU; Harsono et al. 2015; Cieza et al. 2016). In addition, H₂¹⁸O has already been observed toward four of these objects (Jørgensen & van Dishoeck 2010; Persson et al. 2012, 2013). The only thing lacking is thus high-spatial resolution images of H¹³CO⁺. Here, we present NOEMA observations of H¹³CO⁺ toward one source, IRAS2A, and compare these to the H₂¹⁸O emission presented by Persson et al. (2012). IRAS2A is a deeply embedded Class 0 protostar in the NGC 1333 region of the Perseus molecular cloud. The quadruple outflows suggest that it is a close binary (Jørgensen et al. 2004a), which has recently been confirmed (0''.6 separation; Tobin et al. 2015). Similar to Persson et al. (2012) we adopt a distance of 250 pc (Enoch et al. 2006).

The observations and results are presented in Sects. 2 and 3, and compared with the H₂¹⁸O observations from Persson et al. (2012). In Sect. 4, the integrated H¹³CO⁺ emission is analyzed using 1D radiative transfer modeling of a spherical envelope with a parametrized H¹³CO⁺ abundance profile. In addition, this abundance profile is validated against the outcome of a full chemical network and low-resolution DCO⁺ observations. The main conclusions, including that we confirm the predicted anticorrelation between H¹³CO⁺ and H₂¹⁸O, are summarized in Sect. 5.

2. Observations

IRAS2A ($\alpha(2000) = 03^{\text{h}}28^{\text{m}}55^{\text{s}}.58$; $\delta(2000) = 31^{\circ}14'37''.10$) was observed using the Northern Extended Millimeter Array (NOEMA) on December 1, 2015 (C configuration), and April 9, 2016 (B configuration) for a total of 2.3 h on source in B configuration and 1.2 h in C configuration. Combining the observations in the different configurations, the data cover baselines from 16.8 to 456.9 m (14.5 to 396.6 k λ). The receivers were tuned to the H¹³CO⁺ $J = 3 - 2$ transition at 260.255 GHz (1.15 mm), and the narrowband correlator was set up with one unit (bandwidth of 40 MHz) centered on this frequency providing a spectral resolution of 0.078 MHz (0.09 km s⁻¹). In addition, the WideX correlator was used, covering a 3.6 GHz window (259.2–262.8 GHz) at a resolution of 1.95 MHz (2.2–2.3 km s⁻¹).

Calibration and imaging were performed using the CLIC and MAPPING packages of the IRAM GILDAS software¹. The standard calibration procedure was followed using the quasars 3C454.3 and 3C84 to calibrate the bandpass, 0333+321 to calibrate the complex gains, and the point sources MWC349 and LkH α 101 to calibrate the absolute flux scale. The continuum visibilities were constructed from line-free channels in the WideX spectrum, and the continuum was subtracted from the

¹ <http://www.iram.fr/IRAMFR/GILDAS>




Fig. 1. Channel maps for the H¹³CO⁺ $J = 3 - 2$ transition. Black contours are in steps of 10σ , starting from a 3σ level (30 mJy beam^{-1} in 0.09 km s^{-1} channels), and the -3σ contours are shown in blue. The peak intensity is $324 \text{ mJy beam}^{-1}$ at 7.68 km s^{-1} ($v_{\text{lsr}} + 0.68 \text{ km s}^{-1}$). The continuum peak position is indicated with a cross and the beam is shown in the bottom left corner of the *bottom left panel*. Channel velocities with respect to the systemic velocity of $v_{\text{lsr}} \approx 7.0 \text{ km s}^{-1}$ are listed in the top right corner of each panel. For the adopted distance to IRAS2A, $1''$ corresponds to 250 AU.

Table 1. Overview of the molecular line observations toward IRAS2A.

Transition	Frequency (GHz)	E_{up}/k (K)	Beam ($''$)	Δv^a (km s^{-1})
H ¹³ CO ⁺ $J = 3 - 2$	260.255	25	0.93×0.68	0.09
H ₂ ¹⁸ O $3_{1,3} - 2_{2,0}$	203.408	204	0.87×0.72	0.115
DCO ⁺ $J = 2 - 1$	144.068	10	2.1×1.7	4.06

Notes. ^(a) Velocity resolution.

line data before imaging. Both the line and continuum data were imaged using default robust weighting. For H¹³CO⁺ this resulted in a $0''.93 \times 0''.68$ (PA = 36°) beam, which is comparable to the beam of the H₂¹⁸O observations (see below), and a rms of 10 mJy beam^{-1} in 0.09 km s^{-1} channels. The continuum image has a $0''.95 \times 0''.65$ (PA = 27°) beam. The continuum flux obtained from a Gaussian fit to the visibilities is 347 mJy .

This is consistent with previous observations between 0.8 and 1.47 mm (Jørgensen et al. 2007; Persson et al. 2012; Taquet et al. 2015) within the 20% flux calibration error, assuming a power-law spectrum for thermal dust emission ($F_\nu \propto \nu^\alpha$, with $\alpha \sim 2.0 - 2.4$). The (u, v) -fitted continuum peak position ($\alpha(2000) = 03^{\text{h}}28^{\text{m}}55^{\text{s}}.57$; $\delta(2000) = 31^\circ 14' 36''.92$) is located $\sim 0''.1$ south of the bright component of the $0''.6$ binary identified by Tobin et al. (2015).

The H₂¹⁸O $3_{1,3} - 2_{2,0}$ transition at 203.408 GHz (1.47 mm) was observed using the Plateau de Bure Interferometer (PdBI) in December 2009 and March 2010 and was presented by Persson et al. (2012). The data have a spectral resolution of 0.087 MHz (0.115 km s^{-1}) and a resulting beam size of $0''.87 \times 0''.72$ (PA = 63.5°) using natural weighting.

In addition, IRAS2A was observed using the PdBI in July, August, and November 2010 and March 2011 in the C and D configurations as part of a study of complex organic molecules toward low-mass protostars (Taquet et al. 2015). The WideX backends were used at $\sim 145 \text{ GHz}$ providing a




Fig. 2. Integrated intensity map for the H^{13}CO^+ $J = 3 - 2$ transition (color scale) toward IRAS2A. The 1.2 mm continuum is overlaid in white contours (top panel) and the H_2^{18}O $3_{1,3} - 2_{2,0}$ transition in blue contours (middle panel). The continuum contours are $1.8 (1\sigma) \times [3, 10, 25, 50, 75]$ mJy beam $^{-1}$, and the H_2^{18}O contours are $9.8 (1\sigma) \times [3, 8, 15, 25, 35]$ mJy beam $^{-1}$ km s $^{-1}$. The beams are depicted in the bottom left corner. The position of the continuum peak is indicated by a black cross (the close binary is unresolved in these data) and the outflow axes by red and blue arrows. The integrated intensities along the dashed white line are shown in the bottom panel, normalized to their maximum value. The zero flux level and source position are indicated by dotted lines.

bandwidth of 3.6 GHz with a spectral resolution of 1.95 MHz ($\sim 3.5 - 4$ km s $^{-1}$). One of the targeted lines was the DCO^+ $J = 2 - 1$ transition at 144.068 GHz. Phase and amplitude were calibrated by performing regular observations of the nearby point sources 3C454.3, 3C84, and 0333+321. Imaging with natural weighting resulted in a $2''.1 \times 1''.7$ (PA = -155°) beam.

An overview of the observed molecular lines and their parameters is provided in Table 1.




Fig. 3. Integrated intensity maps for a spherically symmetric ring-shaped H^{13}CO^+ distribution. Emission simulated with the radiative transfer code Ratran is convolved with the observed beam (left panel), and simulated with the (u, v) coverage of the NOEMA observations (right panel). The southern peak in the simulations is probably not observed owing to presence of water in the outflow (see text for details). The continuum peak is denoted with a cross, and the beam is shown in the bottom left corner.




Fig. 4. Spectra extracted in a beam toward the continuum peak position (left panels) and the H^{13}CO^+ peak position ($\sim 2''$ NE of the continuum peak, right panels). The top panels show the H^{13}CO^+ $J = 3 - 2$ transition and the bottom panels show the H_2^{18}O $3_{1,3} - 2_{2,0}$ transition. The two spectra for each species are shown on the same vertical scale. The systemic velocity is indicated by the vertical dotted line at $v_{\text{lsr}} \approx 7$ km s $^{-1}$.

3. Results

The H^{13}CO^+ channel maps presented in Fig. 1 show detection of H^{13}CO^+ at velocities between 6.2 and 8.4 km s $^{-1}$ ($v_{\text{lsr}} = 7.0$ km s $^{-1}$; Persson et al. 2012), although the emission is brightest for the redshifted velocities. In none of the channels does the H^{13}CO^+ emission peak at the source position. Instead, emission peaks are observed at offsets (RA, Dec) of approximately $(2'', 1.5'')$ and $(-3'', -3'')$ in the redshifted channels, and at $(-1'', -6'')$ in the blueshifted channels. H_2^{18}O , on the other hand, shows compact emission on source (located by Persson et al. 2012, $\sim 0''.1$ southwest of the continuum peak) and extends along

the southern outflow axis. Overlaying the integrated intensity maps for H¹³CO⁺ and H₂¹⁸O (see Fig. 2) shows that the H¹³CO⁺ emission surrounds the water emission and peaks $\sim 2''$ northeast of the continuum peak.

The asymmetry in the spatial distribution of the H¹³CO⁺ emission is partly due to the sampling of the (u, v) plane; simulating emission from a spherical envelope model with a ring-like H¹³CO⁺ abundance distribution using the same (u, v) coverage as the observations results in emission peaks in the northeast and southwest rather than a spherically symmetric emission pattern (see Fig. 3). The absence of a strong southwestern peak in the data may be attributed to the presence of water in the southern outflow. Alternatively, it could be an effect of the 3D structure of the source, which causes the H¹³CO⁺ emission from that part to be blocked. Finally, it could perhaps be the result of asymmetries in the initial filamentary structure at large scales ($\gg 10\,000$ AU).

Spectra for H¹³CO⁺ and H₂¹⁸O extracted toward the continuum and H¹³CO⁺ peak positions are presented in Fig. 4. Although there is still H¹³CO⁺ emission present on source, it is reduced by $\sim 40\%$ compared to the region in which water emission is absent. The narrow width ($FWHM \approx 0.8$ km s⁻¹) of the H¹³CO⁺ line at its peak position indicates that the emission does not originate in the outflow. In comparison, the H₂¹⁸O line width is ~ 3.5 km s⁻¹. In addition, it has been shown in Persson et al. (2012) that the outflow component of the H₂¹⁸O emission can be distinguished spatially from the compact component. The emission around $v_{lsr} = 3$ km s⁻¹ in the H₂¹⁸O spectrum is due to dimethyl ether (CH₃OCH₃; Persson et al. 2012).

The absorption feature for H¹³CO⁺ around the systemic velocity is partly because emission from the large-scale envelope is resolved out, as can be seen from the channel maps in Fig. 1 where most of the emission is absent around the systemic velocity. In addition, a comparison with JCMT single dish observations from Jørgensen et al. (2004b) shows that only $\sim 7\%$ of the peak flux is recovered in the NOEMA observations, demonstrating that the bulk of the H¹³CO⁺ is located on larger scales. Imaging the data before continuum subtraction shows that some absorption also occurs against the continuum in the central channels, which is indicative of cold gas along the line of sight at scales larger than the scale of interest.

4. Analysis and discussion

4.1. Parametrized abundance profile for H¹³CO⁺

To establish the origin of the dip in the H¹³CO⁺ emission at the central position, 1D spherically symmetric physical-chemical modeling was performed using the radiative transfer code Ratran (Hogerheijde & van der Tak 2000). For the physical structure we adopted the temperature and density profiles for IRAS2A from Kristensen et al. (2012), derived using the 1D spherically symmetric dust radiative transfer code DUSTY (Ivezić & Elitzur 1997). In this procedure the free model parameters were fitted to the spectral energy distribution (SED) and the spatial extent of the sub-mm continuum emission. Based on the chemical consideration that H¹³CO⁺ is particularly abundant when its main destructor H₂O is frozen out, the simplest H¹³CO⁺ distribution is an abundance profile with a low abundance inside the 100 K radius (i.e., the water snowline) and a higher abundance at larger radii. Both the inner and outer abundances are varied to get the best match to the observed integrated intensity along




Fig. 5. Various H¹³CO⁺ abundance profiles (*left panels*) and the resulting simulated integrated emission along the northeastern part of the radial cut shown in Fig. 2 (*right panels*). The observed emission is shown in purple. The location of the abundance jumps (in Kelvin and AU) is indicated in the top right corners. *Bottom panel*: temperature (gray) and density (blue) profiles for the IRAS2A envelope from Kristensen et al. (2012) used in the top two models. The location of the H₂O and CO snowlines (at 100 K and 20 K, resp.) are indicated by the dotted red and blue lines, respectively. The temperature profile increased by a factor of 2.2, used in the bottom two models, is shown in black. The resulting H₂O snowline is indicated by the dashed red line while the CO snowline now falls outside the adopted radial range. For IRAS2A, 1'' corresponds to ~ 250 AU.

the radial cut shown in Fig. 2. The absence of the southwest H¹³CO⁺ peak (discussed in Sect. 3) cannot be modeled with an axisymmetric 1D model. We therefore restrict the comparison to the northeastern part of the radial cut. For a first analysis, we do not adopt a velocity structure. The difference between the blue- and redshifted channels then cannot be reproduced exactly. Since there is almost no emission along the radial cut in the




Fig. 6. *Left panels:* temperature (gray) and density (blue) profiles for the IRAS2A envelope from [Kristensen et al. \(2012\)](#) (*top*), and the corresponding H₂O (light blue), CO (blue), and HCO⁺ (purple) abundances predicted by the GRAINOBLE model (*bottom*). The dashed green line shows the empirically inferred abundance profile for H¹³CO⁺ (scaled down by a factor 100). *Right panels:* as *left panels*, but with the temperature increased by a factor 2.2. The vertical dotted lines indicate the H₂O and CO snowlines.

blueshifted channels, only the redshifted channels are used to construct the zeroth moment maps. Including all channels does not significantly change the observed integrated radial profile, but only affects the H¹³CO⁺ abundance required to reach the observed intensity (by a factor of ~ 3). However, deriving the precise H¹³CO⁺ abundance is not the goal of this work. Finally, simulated images representing the observed (u, v) coverage are produced from the Ratan images in GILDAS by creating a (u, v) table with the function `uv_fmodel`.

Various H¹³CO⁺ abundance profiles with their corresponding integrated emission profiles are presented in Fig. 5. For the adopted physical structure, the temperature drops below 100 K around 90 AU. An H¹³CO⁺ abundance of 1×10^{-10} at radii > 90 AU can roughly reproduce the observed integrated intensity (Fig. 5, second row). However, independent of the inner abundance, the emission always peaks on source, as in the case of a constant H¹³CO⁺ abundance at all radii (Fig. 5, top row). Although a large percentage ($\sim 90\%$) of the emission is already being resolved out with the (u, v) coverage of the observations, this thus does not result in a dip in the H¹³CO⁺ emission toward the source position.

To reproduce the location of the emission peak, the abundance jump has to be shifted outward to a radius of ~ 360 AU. To move the 100 K radius, representing the water snowline, this far out, the temperature profile has to be multiplied by a factor of 2.2 (Fig. 5, third row). However, the observed integrated intensity cannot be reached with this abundance profile, as the H¹³CO⁺ emission becomes optically thick for outer abundances higher than 3×10^{-10} . Varying the abundance does not affect the position of the emission peak.

The best match to the observed H¹³CO⁺ radial profile can be reached by introducing an additional drop in the abundance around ~ 4000 AU (Fig. 5, fourth row). An increase in abundance

of at least a factor of six is required around 360 AU to get the emission peak at the observed location, but the exact radius of the outer drop does not influence the peak position. Such a decrease in the H¹³CO⁺ abundance can be expected around the CO snowline because formation of HCO⁺ is limited in this region because of a reduction in the parent gaseous CO molecules. A radius of 4000 AU corresponds to 17 K for the [Kristensen et al. \(2012\)](#) temperature profile, consistent with the CO freeze-out temperature for a pure CO ice binding energy. In contrast, for the increased temperature profile the temperature is 38 K at this radius; temperatures below 20 K are not reached within the 20 000 AU radial extent of the model. An increased temperature is thus required to set the inner radius of the H¹³CO⁺ abundance at the water snowline, while the original temperature places the outer radius around the CO snowline. This discrepancy is further discussed in Sects. 4.2 and 4.3. The main result of these models is that the observed position of the H¹³CO⁺ emission peak can only be reproduced by a reduction in the abundance of at least a factor 6 in the inner ~ 360 AU.

4.2. Comparison with a full chemical model

To inspect the legitimacy of the simple abundance profile, we compared it to the outcome of the astrochemical code GRAINOBLE ([Taquet et al. 2012a,b, 2013, 2014](#)). In short, GRAINOBLE uses the rate equations approach ([Hasegawa et al. 1992](#)) considering three types of reactions (a so-called three-phase model based on [Hasegawa & Herbst 1993](#)): reactions for gas-phase species, reactions for species on the ice surface, and reactions for bulk ice species. The gas-phase chemical network is taken from the KIDA database ([Wakelam et al. 2015](#)) supplemented by ion-neutral reactions described in [Taquet et al. \(2016\)](#). A cosmic

ray (CR) ionization rate of $5 \times 10^{-17} \text{ s}^{-1}$ is used. In addition to thermal desorption, UV photodesorption and chemical desorption upon formation of an exothermic surface reaction have been included as desorption processes. The surface chemical network follows the results of recent laboratory experiments to form the main ice species (see Taquet et al. 2013, for references). For CO and H₂O binding energies have been adopted for an amorphous water ice substrate: 1150 K and 5775 K, respectively (Collings et al. 2004; Fraser et al. 2001). The formation of interstellar ices is first followed during the formation of a dense starless core with the method described in Taquet et al. (2014). This ice chemical composition is then used as initial conditions for the gas-grain chemical evolution around IRAS2A, adopting the static 1D physical profile derived by Kristensen et al. (2012). Surface reactions have a negligible impact on the HCO⁺ abundance during the latter protostellar phase. They have a significant importance during the former prestellar phase since they govern the transformation of CO ice into other species, thereby setting the initial ice abundance for the protostellar phase. The initial gas-phase abundances and ice abundances at the start of the protostellar phase are listed in Appendix A.

The left panel of Fig. 6 presents the H₂O, CO and HCO⁺ abundances for the IRAS2A envelope structure after 10⁴ yr of chemical evolution. The abundance profiles do not change significantly for evolution up to ~10⁵ yr, that is, the duration of the protostellar phase. Going from the outer envelope inward, the temperature rises above 20 K at a radius of ~2700 AU, causing CO to desorb from the ice surface into the gas phase. In the three-phase model, a significant part of the icy CO remains trapped in the ice matrix at temperatures higher than the CO desorption temperature. These CO molecules evaporate together with water when the temperature exceeds ~100 K, resulting in a double abundance jump profile for CO. The water snowline, that is, the radius where 50% of the water is in the gas phase and 50% is frozen out, is located at a distance of ~65 AU from the protostar (corresponding to 127 K). As expected, the HCO⁺ abundance increases sharply at radii beyond the water snowline, where its main destructor is frozen out, and decreases again outside the CO snowline, where the availability of its parent molecule is reduced. Increasing the temperature by a factor of 2.2, as was required to match the observed H¹³CO⁺ emission with a drop in the abundance at the 100 K radius, results in a similar chemical profile, only with the snowlines shifted to larger radii (Fig. 6, right panel). The water snowline is now located at ~225 AU (127 K), while the CO snowline falls outside the modeled radial range. The water snowline location matches the observed radial extent of the H₂¹⁸O emission (~1'' ≈ 250 AU).

For comparison, the best H¹³CO⁺ abundance profile derived from the data is added to Fig. 6 (dashed green line). This inferred H¹³CO⁺ abundance is higher than expected based on the GRAINOBLE results: similar to the predicted HCO⁺ abundance instead of a factor ~70 lower. This can most likely be explained by the relatively low CO abundance between the CO and H₂O snowlines in the chemical model, which directly results in a low HCO⁺ abundance. The CO abundance is low because a large percentage of the CO ice is converted into methanol during the prestellar phase (Table A.2). In addition, in the three-phase model, not all CO evaporates inside its snowline, but remains trapped in water ice (Fig. 6). However, it is the overall trend that the HCO⁺ abundance sharply rises at the H₂O snowline and drops at the CO snowline that is important.

The radius where H¹³CO⁺ has to increase (360 AU) matches the inner radius of the HCO⁺ distribution in the chemical network with the increased temperature profile (right panel). The water snowline, however, is located ~135 AU closer to the star, at 225 AU. Similar behavior is seen in models for N₂H⁺; the 50% reduction in CO, or in this case H₂O, at the snowline is not yet sufficient to diminish the destruction of N₂H⁺ or HCO⁺, respectively, moving the emission ring outward (Aikawa et al. 2015; van 't Hoff et al. 2017). There are thus two effects at play here: first, the HCO⁺ abundance is expected to peak outside rather than directly at the water snowline (360 vs. 225 AU). Second, this location for the water snowline is further away from the protostar than expected based on the Kristensen et al. (2012) temperature profile (225 vs. 65 AU).

The outer drop in H¹³CO⁺ abundance matches less well with the predicted HCO⁺ distributions. The best agreement is for the original temperature profile (for the adopted CO binding energy of 1150 K), although HCO⁺ decreases ~2000 AU (2.4 K) further in than the radiative transfer modeling derived from the H¹³CO⁺ data. Owing to the shallow gradient of the temperature profile in the outer envelope, the exact location of the CO snowline is very sensitive to small changes in the thermal structure. The mismatch could therefore be due to uncertainties in the derived temperature. Another important parameter for the snowline location is the assumed binding energy for CO, which is related to the assumed ice structure, that is, whether CO ice is mixed with other molecules or pure. Adopting a lower binding energy, corresponding to a CO ice substrate rather than a H₂O ice substrate, would shift the snowline to larger radii. Anderl et al. (2016) investigated the CO binding energy using NOEMA observations of C¹⁸O and N₂H⁺ toward four young protostars and concluded that the extent of the C¹⁸O emission was best reproduced using a CO binding energy of 1200 K, corresponding to a water ice substrate. In addition, these authors showed that the freeze-out temperature is ~6 K lower assuming a binding energy of 855 K for pure CO ice instead of 1200 K. Since the temperature difference between the CO snowline and the location of the H¹³CO⁺ drop is only 2.4 K, a high CO binding energy also seems best for IRAS2A. The small discrepancy between the CO snowline location predicted by the chemical model and the location inferred from the H¹³CO⁺ observations may then be the result of asymmetries in IRAS2A, as hinted at by the asymmetric C¹⁸O emission shown by Anderl et al. (2016) for other protostars.

As noted before, the exact location of the drop in H¹³CO⁺ in the outer envelope does not influence the observed position of the emission peak. The main point is that the chemical model indeed predicts a steep rise in HCO⁺ abundance just outside the water snowline, and a drop outside the CO snowline. This justifies the abundance profile used in the radiative transfer modeling, and corroborates that the depression in H¹³CO⁺ in the center is due to the presence of gas-phase water.

4.3. Tracing the CO snowline: signs of an accretion burst?

Having the snowlines located further out than expected based on the adopted temperature profile derived from SED models, such as found here for the water snowline, could be a sign that the protostar has recently undergone a luminosity outburst. Such an outburst heats up the envelope, causing ices to sublimate off the grains. After the burst, the envelope cools rapidly (Johnstone et al. 2013), while it takes much longer for the molecules to freeze back onto the dust grains (Rodgers & Charnley 2003). As a result, snowlines are shifted away from the star (Visser et al. 2015; Jørgensen et al. 2015; Cieza et al. 2016;




Fig. 7. H₂O (light blue), CO (blue), HCO⁺ (purple), and DCO⁺ (pink) abundances predicted by the GRAINOBLE model for the IRAS2A temperature and density profile from Kristensen et al. (2012). The vertical dotted lines indicate the H₂O and CO snowlines.

Frimann et al. 2017). An increased temperature structure is required to fit the H¹³CO⁺ emission, suggesting that the water snowline is further out than expected. In case of an outburst, the CO snowline would also be shifted outward. Observational constraints for the CO snowline can thus help to establish whether IRAS2A has indeed recently undergone an accretion burst.

The deuterated form of HCO⁺, DCO⁺, can be used to trace the freeze-out of CO (e.g., Mathews et al. 2013). DCO⁺ forms via reaction of H₂D⁺ and CO. Formation of H₂D⁺ is enhanced at low temperatures (<30 K), but below ~20 K CO starts to freeze-out. This balance results in DCO⁺ peaking around the CO snowline (Murillo et al. 2015). Contamination of the emission by DCO⁺ formed in warmer layers from CH₂D⁺ is not likely to be important in protostellar envelopes, unlike in protoplanetary disks (Favre et al. 2015). The DCO⁺ abundance profile for the IRAS2A envelope structure is predicted with GRAINOBLE by extending the chemical network with a small network that includes reactions between CO and H₂D⁺, HD₂⁺ and D₃⁺. The DCO⁺ abundance indeed peaks around the CO snowline (see Fig. 7), which is located at ~2000 AU for the fiducial temperature structure. As such, DCO⁺ emission can be used to estimate the CO snowline location and constrain the temperature profile in the envelope.

The observed integrated intensity map for DCO⁺ toward IRAS2A is presented in Fig. 8. Emission is observed south of the continuum peak and peaks ~10'' off source. Such an asymmetric emission pattern is observed for more protostars (e.g., Murillo et al. 2015). A CO snowline around ~2000 AU, as predicted by the chemical model for the Kristensen et al. (2012) temperature profile, is in agreement with the DCO⁺ emission. Thus, although the H₂O snowline is located at larger radii than predicted based on the IRAS2A temperature profile (225 vs. 65 AU), the location of the CO snowline is as expected. Since the chemical reset after an outburst is faster at high densities, it is unlikely that the CO snowline has already shifted back while the H₂O snowline has not. In addition, Jørgensen et al. (2015) presented C¹⁸O images obtained with the Submillimeter Array (SMA) for which the spatial extent matches well with the current luminosity. It is thus unlikely that IRAS2A has recently undergone an accretion burst. Why the temperature profile matches the snowline location for CO but not for H₂O is further discussed in Sect. 4.5.




Fig. 8. Integrated intensity map for the H¹³CO⁺ $J = 3 - 2$ transition (color scale) toward IRAS2A. The DCO⁺ $J = 2 - 1$ transition is overlaid in pink contours. Contours are shown in steps of 1σ starting from a 3σ level ($15 \text{ mJy beam}^{-1} \text{ km s}^{-1}$). The beams are depicted in the bottom left corner. The position of the continuum peak is indicated by a white cross and the outflow axes by red and blue arrows. The length of the arrows is the same as in Fig. 2 to compare the scales. The solid white contour represents the CO snowline radius predicted by the chemical model for the Kristensen et al. (2012) temperature profile (~2000 AU).

4.4. Attenuation of the cosmic ray ionization rate

The chemistry leading to the formation of HCO⁺ is initiated by the ionization of H₂ molecules by cosmic rays (CRs). A reduction in the CR ionization rate therefore results in a lower HCO⁺ abundance. Numerical simulations performed by Padovani et al. (2013) showed that the CR ionization rate can be reduced by an order of magnitude in the inner region of a collapsing cloud core owing to twisting of the magnetic field lines. However, the exact value of the CR ionization rate in the inner regions of protostellar envelopes is unknown, and more recent work by Padovani et al. (2015, 2016) has shown that jet shocks and protostellar surface shocks can drive particle acceleration, leading to increased CR ionization rates.

Nonetheless, to assess if the effect of CR attenuation is large enough to cause the drop in H¹³CO⁺ emission that we observe, we performed an order of magnitude calculation. As such, we approximate the reactions producing H₃⁺ upon CR ionization by



where ζ_{CR} is the CR ionization rate. In this formalism we ignore H₂⁺, as the ionization is the rate limiting step for H₃⁺. Formation of HCO⁺ is dominated by the reaction between H₃⁺ and CO,



and to estimate the importance of CRs, only recombination is considered as destruction reaction for HCO⁺, that is,



Assuming steady state and $n(e^-) \approx n(\text{HCO}^+)$, the following relation can then be derived between the HCO⁺ density, $n(\text{HCO}^+)$, and the CR ionization rate, ζ_{CR} (see Appendix B for more details):

$$n(\text{HCO}^+) = \sqrt{\frac{\zeta_{\text{CR}} n(\text{H}_2)}{k}}, \quad (5)$$

where $n(\text{H}_2)$ is the molecular density of H₂ and k is the reaction rate coefficient for the HCO⁺ destruction reaction (Eq. (4)). From this it can be seen that an order of magnitude reduction in the CR ionization rate gives a factor of three reduction in HCO⁺ abundance. Based on our radiative transfer modeling, at least a factor of six is required to fit the observations. Attenuation of the CR ionization rate alone is thus not likely to be the cause of the observed reduced H¹³CO⁺ emission toward the center of IRAS2A.

4.5. Physical structure

Finally, a more likely explanation for the discrepancy between the temperatures needed for the CO and H₂O snowlines may be that the physical structure of IRAS2A is more complicated than assumed with the 1D model. For several young protostars, it has been shown that a spherical envelope model cannot reproduce all of the continuum emission on small scales (e.g., Hogerheijde et al. 1999; Looney et al. 2003). This is also the case for IRAS2A (Brown et al. 2000; Jørgensen et al. 2005) and Persson et al. (2016) have derived the presence a compact disk-like structure with a 167^{+63}_{-21} AU radius. The density may therefore change significantly on these scales of disk-envelope transition, that is, the scale at which we observe the H₂¹⁸O-H¹³CO⁺ anticorrelation. Since the envelope around IRAS2A is relatively optically thick to its own infrared radiation on ~100 AU scales, the exact temperature distribution becomes very dependent on the assumption about the density structure. In addition, the presence of an outflow cavity can shift the 100 K radius outward in specific directions (Bjerkeli et al. 2016), as the temperature along the cavity wall is higher at certain radii than in the envelope mid-plane (Visser et al. 2012). However, these considerations do not affect the main conclusion that the observations show a clear anticorrelation between H₂¹⁸O and H¹³CO⁺ emission.

5. Summary and outlook

We have presented subarcsecond resolution observations of the H¹³CO⁺ $J = 3 - 2$ transition at 260.255 GHz toward the Class 0 protostar IRAS2A, and for the first time, compared these directly to observations of H₂¹⁸O, which were presented by Persson et al. (2012). While the H₂¹⁸O $3_{1,3} - 2_{2,0}$ emission is centered at the continuum peak within a ~1'' radius, the H¹³CO⁺ emission peaks ~2'' to the northeast.

Using a 1D envelope model for IRAS2A, this offset in H¹³CO⁺ emission can be explained by an abundance decrease of at least a factor of six in the inner ~360 AU, but not by a constant H¹³CO⁺ abundance. An increase in H¹³CO⁺ abundance just outside the water snowline is consistent with chemical model predictions; the water snowline is then located around 225 AU, whereas the H¹³CO⁺ abundance peaks ~135 AU further out at 360 AU. This snowline radius is larger than expected if the 1D spherically symmetric temperature profile from Kristensen et al. (2012) is adopted. DCO⁺ observations place the CO snowline at the expected location, making an outburst scenario unlikely.

The combined observations of H¹³CO⁺ and H₂¹⁸O, together with radiative transfer and chemical modeling, thus provide proof of concept for the HCO⁺-H₂O anticorrelation. The next step would be to corroborate this for more protostellar systems. Establishing H¹³CO⁺ as a good tracer of the water snowline may allow localization of the snowline in protoplanetary disks for which direct detection is very difficult.

Acknowledgements. We would like to thank the referee for useful comments. In addition, we are grateful to the IRAM staff, in particular Miguel Montargès, for his help with the observations and reduction of the data, and Nadia Murillo and Arthur Bosman for useful discussions. Astrochemistry in Leiden is supported by the European Union A-ERC grant 291141 CHEMPLAN, by the Netherlands Research School for Astronomy (NOVA) and by a Royal Netherlands Academy of Arts and Sciences (KNAW) professor prize. M.L.R.H acknowledges support from a Huygens fellowship from Leiden University. M.V.P. postdoctoral position is funded by the ERC consolidator grant 614264. V.T. has received funding from the European Union's Horizon 2020 research and innovation programme under the Marie Skłodowska-Curie grant agreement no. 664931. The research of J.K.J. is supported by European Union ERC Consolidator Grant "S4F" (grant agreement No 646908) and Centre for Star and Planet Formation funded by the Danish National Research Foundation.

References

- Aikawa, Y., Furuya, K., Nomura, H., & Qi, C. 2015, *ApJ*, 807, 120
 Ali-Dib, M. 2017, *MNRAS*, 467, 2845
 Ali-Dib, M., Mousis, O., Petit, J.-M., & Lunine, J. I. 2014, *ApJ*, 785, 125
 Anderl, S., Maret, S., Cabrit, S., et al. 2016, *A&A*, 591, A3
 Bergin, E. A., & van Dishoeck, E. F. 2012, *Roy. Soc. London Philos. Trans. Ser. A*, 370, 2778
 Bergin, E. A., Melnick, G. J., & Neufeld, D. A. 1998, *ApJ*, 499, 777
 Bjerkeli, P., Jørgensen, J. K., Bergin, E. A., et al. 2016, *A&A*, 595, A39
 Booth, R. A., Clarke, C. J., Madhusudhan, N., & Ilee, J. D. 2017, *MNRAS*, 469, 3994
 Brown, D. W., Chandler, C. J., Carlstrom, J. E., et al. 2000, *MNRAS*, 319, 154
 Burke, D. J., & Brown, W. A. 2010, *Phys. Chem. Chem. Phys.*, 12, 5947
 Cieza, L. A., Casassus, S., Tobin, J., et al. 2016, *Nature*, 535, 258
 Collings, M. P., Anderson, M. A., Chen, R., et al. 2004, *MNRAS*, 354, 1133
 Eistrup, C., Walsh, C., & van Dishoeck, E. F. 2016, *A&A*, 595, A83
 Enoch, M. L., Young, K. E., Glenn, J., et al. 2006, *ApJ*, 638, 293
 Favre, C., Bergin, E. A., Cleaves, L. I., et al. 2015, *ApJ*, 802, L23
 Fraser, H. J., Collings, M. P., McCoustra, M. R. S., & Williams, D. A. 2001, *MNRAS*, 327, 1165
 Frimann, S., Jørgensen, J. K., Dunham, M. M., et al. 2017, *A&A*, 602, A120
 Harsono, D., Bruderer, S., & van Dishoeck, E. F. 2015, *A&A*, 582, A41
 Hasegawa, T. I., & Herbst, E. 1993, *MNRAS*, 263, 589
 Hasegawa, T. I., Herbst, E., & Leung, C. M. 1992, *ApJS*, 82, 167
 Hogerheijde, M. R., & van der Tak, F. F. S. 2000, *A&A*, 362, 697
 Hogerheijde, M. R., van Dishoeck, E. F., Salverda, J. M., & Blake, G. A. 1999, *ApJ*, 513, 350
 Hogerheijde, M. R., Bergin, E. A., Brinch, C., et al. 2011, *Science*, 334, 338
 Ivezić, Z., & Elitzur, M. 1997, *MNRAS*, 287, 799
 Johnstone, D., Hendricks, B., Herczeg, G. J., & Bruderer, S. 2013, *ApJ*, 765, 133
 Jørgensen, J. K. 2004, *A&A*, 424, 589
 Jørgensen, J. K., & van Dishoeck, E. F. 2010, *ApJ*, 710, L72
 Jørgensen, J. K., Hogerheijde, M. R., van Dishoeck, E. F., Blake, G. A., & Schöier, F. L. 2004a, *A&A*, 413, 993
 Jørgensen, J. K., Schöier, F. L., & van Dishoeck, E. F. 2004b, *A&A*, 416, 603
 Maret, S., Bourke, T. L., Myers, P. C., et al. 2005, *ApJ*, 632, 973
 Jørgensen, J. K., Bourke, T. L., Myers, P. C., et al. 2007, *ApJ*, 659, 479
 Jørgensen, J. K., Visser, R., Sakai, N., et al. 2013, *ApJ*, 779, L22
 Jørgensen, J. K., Visser, R., Williams, J. P., & Bergin, E. A. 2015, *A&A*, 579, A23
 Kristensen, L. E., van Dishoeck, E. F., Bergin, E. A., et al. 2012, *A&A*, 542, A8
 Looney, L. W., Mundy, L. G., & Welch, W. J. 2003, *ApJ*, 592, 255
 Madhusudhan, N., Amin, M. A., & Kennedy, G. M. 2014, *ApJ*, 794, L12
 Maret, S., Belloche, A., Maury, A. J., et al. 2014, *A&A*, 563, L1
 Mathews, G. S., Klaassen, P. D., Juhász, A., et al. 2013, *A&A*, 557, A132
 Maury, A. J., Belloche, A., André, P., et al. 2014, *A&A*, 563, L2
 Melnick, G. J. 2009, in *Submillimeter Astrophysics and Technology: a Symposium Honoring Thomas, eds. G. Phillips, D. C. Lis, J. E. Vaillancourt, et al. ASP Conf. Ser.*, 417, 59
 Mordasini, C., van Boekel, R., Mollière, P., Henning, T., & Benneke, B. 2016, *ApJ*, 832, 41
 Murillo, N. M., Bruderer, S., van Dishoeck, E. F., et al. 2015, *A&A*, 579, A114
 Öberg, K. I., Murray-Clay, R., & Bergin, E. A. 2011, *ApJ*, 743, L16
 Öberg, K. I., Guzmán, V. V., Furuya, K., et al. 2015, *Nature*, 520, 198
 Padovani, M., Hennebelle, P., & Galli, D. 2013, *A&A*, 560, A114
 Padovani, M., Hennebelle, P., Marcowith, A., & Ferrière, K. 2015, *A&A*, 582, L13
 Padovani, M., Marcowith, A., Hennebelle, P., & Ferrière, K. 2016, *A&A*, 590, A8
 Persson, M. V., Jørgensen, J. K., & van Dishoeck, E. F. 2012, *A&A*, 541, A39

Persson, M. V., Jørgensen, J. K., & van Dishoeck, E. F. 2013, *A&A*, 549, L3

Persson, M. V., Harsono, D., Tobin, J. J., et al. 2016, *A&A*, 590, A33

Phillips, T. G., van Dishoeck, E. F., & Keene, J. 1992, *ApJ*, 399, 533

Qi, C., Öberg, K. I., Wilner, D. J., et al. 2013, *Science*, 341, 630

Qi, C., Öberg, K. I., Andrews, S. M., et al. 2015, *ApJ*, 813, 128

Rodgers, S. D., & Charnley, S. B. 2003, *ApJ*, 585, 355

Schoonenberg, D., & Ormel, C. W. 2017, *A&A*, 602, A21

Stevenson, D. J., & Lunine, J. I. 1988, *Icarus*, 75, 146

Taquet, V., Ceccarelli, C., & Kahane, C. 2012a, *ApJ*, 748, L3

Taquet, V., Ceccarelli, C., & Kahane, C. 2012b, *A&A*, 538, A42

Taquet, V., Peters, P. S., Kahane, C., et al. 2013, *A&A*, 550, A127

Taquet, V., Charnley, S. B., & Sipilä, O. 2014, *ApJ*, 791, 1

Taquet, V., López-Sepulcre, A., Ceccarelli, C., et al. 2015, *ApJ*, 804, 81

Taquet, V., Wirström, E. S., & Charnley, S. B. 2016, *ApJ*, 821, 46

Tobin, J. J., Dunham, M. M., Looney, L. W., et al. 2015, *ApJ*, 798, 61

van Dishoeck, E. F., Herbst, E., & Neufeld, D. A. 2013, *Chem. Rev.*, 113, 9043

van 't Hoff, M. L. R., Walsh, C., Kama, M., Facchini, S., & van Dishoeck, E. F. 2017, *A&A*, 599, A101

Visser, R., Kristensen, L. E., Bruderer, S., et al. 2012, *A&A*, 537, A55

Visser, R., Bergin, E. A., & Jørgensen, J. K. 2015, *A&A*, 577, A102

Wakelam, V., & Herbst, E. 2008, *ApJ*, 680, 371

Wakelam, V., Loison, J.-C., Herbst, E., et al. 2015, *ApJS*, 217, 20

Walsh, C., Nomura, H., & van Dishoeck, E. 2015, *A&A*, 582, A88

Walsh, C., Loomis, R. A., Öberg, K. I., et al. 2016, *ApJ*, 823, L10

Zhang, K., Pontoppidan, K. M., Salyk, C., & Blake, G. A. 2013, *ApJ*, 766, 82

Appendix A: Initial abundances in the GRAINOBLE model

Table A.1 lists the initial elemental abundances in the gas phase for the prestellar phase of the GRAINOBLE model, based on the low-metal model from Wakelam & Herbst (2008). The ice composition at the end of this phase (after 1.7 Myr) is listed in Table A.2. These are the initial conditions for the chemical evolution around IRAS2A.

Table A.1. Initial gas-phase elemental abundances.

Species	Abundance ^a
H ₂	0.5
HD	1.5×10^{-5}
H	1.6×10^{-4}
He	9.0×10^{-2}
C+	7.3×10^{-5}
N	2.1×10^{-5}
O	1.8×10^{-4}
Si	8.0×10^{-9}
S	8.0×10^{-8}
Fe	3.0×10^{-9}
Na	2.0×10^{-9}
Mg	7.0×10^{-9}
Cl	1.0×10^{-9}

Notes. ^(a) Abundances with respect to the total number of hydrogen nuclei.

Appendix B: Effect of an attenuated cosmic ray ionization rate

A first order approximation of the effect of CR ionization rate on the HCO⁺ abundance can be made by considering the main formation and destruction reactions of HCO⁺. Assuming steady state, that is, assuming that the HCO⁺ abundance does not

Table A.2. Ice chemical composition at the end of the prestellar phase.

Species	Abundance ^a
H ₂ O	1.1×10^{-4}
CO	1.3×10^{-5}
CO ₂	1.7×10^{-7}
N ₂	9.8×10^{-6}
H ₂ CO	6.7×10^{-5}
CH ₃ OH	5.5×10^{-5}
NH ₃	1.3×10^{-6}
CH ₄	4.4×10^{-6}

Notes. ^(a) Abundances with respect to the total number of hydrogen nuclei.

change over time, we can write

$$\frac{dn(\text{HCO}^+)}{dt} = \text{formation rate} - \text{destruction rate} = 0. \quad (\text{B.1})$$

The main formation pathway of HCO⁺ is through reaction between CO and H₃⁺,



and recombination with electrons is the main destruction route,



The reaction of HCO⁺ with H₂O is ignored in this calculation to assess the importance of the CR ionization rate.

The rate of these reactions can be written as

$$\text{rate} = k \times n(A)n(B), \quad (\text{B.4})$$

where k is the rate coefficient, and $n(A)$ and $n(B)$ are the molecular densities of the reacting species. Equation (B.1) then becomes

$$k_1 n(\text{H}_3^+)n(\text{CO}) - k_2 n(\text{HCO}^+)n(\text{e}^-) = 0. \quad (\text{B.5})$$

The H₃⁺ density, $n(\text{H}_3^+)$, can be calculated by following the same procedure. The formation reactions are



In order to solve Eq. (B.5) analytically, we summarize the formation of H₃⁺ as follows:



because the ionization reaction is the rate limiting step. In addition, only the reaction with CO (Eq. (B.3)) is considered as destruction mechanism. We can then write an equation similar to Eq. (B.5), that is,

$$\zeta_{\text{CR}}n(\text{H}_2) - k_1 n(\text{H}_3^+)n(\text{CO}) = 0. \quad (\text{B.9})$$

Substituting Eq. (B.9) into Eq. (B.5), and assuming $n(\text{e}^-) \approx n(\text{HCO}^+)$, we can solve Eq. (B.5) to get the following expression for the HCO⁺ density:

$$n(\text{HCO}^+) = \sqrt{\frac{\zeta_{\text{CR}}n(\text{H}_2)}{k_2}}. \quad (\text{B.10})$$