



Stationary optomechanical entanglement between a mechanical oscillator and its measurement apparatus

Downloaded from: <https://research.chalmers.se>, 2026-04-03 06:27 UTC

Citation for the original published paper (version of record):

Gut, C., Winkler, K., Hoelscher-Obermaier, J. et al (2020). Stationary optomechanical entanglement between a mechanical oscillator and its measurement apparatus. *PHYSICAL REVIEW RESEARCH*, 2(3).
<http://dx.doi.org/10.1103/PhysRevResearch.2.033244>

N.B. When citing this work, cite the original published paper.

Stationary optomechanical entanglement between a mechanical oscillator and its measurement apparatus

C. Gut^{1,2,*}, K. Winkler^{1,*}, J. Hoelscher-Obermaier¹, S. G. Hofer^{1,2}, R. Moghadas Nia¹, N. Walk³, A. Steffens³, J. Eisert³, W. Wieczorek^{1,†}, J. A. Slater^{1,‡}, M. Aspelmeyer^{1,4} and K. Hammerer²

¹Vienna Center for Quantum Science and Technology (VCQ), Faculty of Physics, University of Vienna, A-1090 Vienna, Austria

²Institute for Theoretical Physics and Institute for Gravitational Physics (Albert-Einstein-Institute), Leibniz University Hannover, 30167 Hannover, Germany

³Dahlem Center for Complex Quantum Systems, Physics Department, Freie Universität Berlin, 14195 Berlin, Germany

⁴Institute for Quantum Optics and Quantum Information (IQOQI), Austrian Academy of Sciences, A-1090 Vienna, Austria



(Received 4 December 2019; accepted 17 June 2020; published 12 August 2020)

We provide an argument to infer stationary entanglement between light and a mechanical oscillator based on continuous measurement of light only. We propose an experimentally realizable scheme involving an optomechanical cavity driven by a resonant, continuous-wave field operating in the non-sideband-resolved regime. This corresponds to the conventional configuration of an optomechanical position or force sensor. We show analytically that entanglement between the mechanical oscillator and the output field of the optomechanical cavity can be inferred from the measurement of squeezing in (generalized) Einstein-Podolski-Rosen quadratures of suitable temporal modes of the stationary light field. Squeezing can reach levels of up to 50% of noise reduction below shot noise in the limit of large quantum cooperativity. Remarkably, entanglement persists even in the opposite limit of small cooperativity. Viewing the optomechanical device as a position sensor, entanglement between mechanics and light is an instance of object-apparatus entanglement predicted by quantum measurement theory.

DOI: [10.1103/PhysRevResearch.2.033244](https://doi.org/10.1103/PhysRevResearch.2.033244)

I. INTRODUCTION

Experiments in optomechanics now operate routinely in a regime in which effects predicted by quantum theory can be observed. This includes mechanical oscillators cooled to their ground state of center-of-mass motion [1,2], ponderomotive squeezing [3–5], entanglement between different light tones [6,7], entanglement between different mechanical oscillators [8,9], measurement back-action [10], back-action evasion [11–13], and optomechanical entanglement, that is, entanglement between the mechanical oscillator and light, in a pulsed regime [14,15].

It has been a long-standing prediction by Genes *et al.* [16] that optomechanical entanglement persists under certain conditions in steady state under continuous-wave drive, see Ref. [17] for a comprehensive review. As explained in Ref. [18], the experimental verification of entanglement between light and the mechanical oscillator is very challenging

because the state of the latter is not accessible directly. The quantum state of the oscillator can, in principle, be reconstructed from measurements on light and suitable postprocessing, as described in Refs. [19–21] and demonstrated in Ref. [22]. In particular, Miao *et al.* [20] have discussed how stationary optomechanical entanglement can be inferred from such a complete quantum state tomography relying on temporally ordered preparation and verification steps. This approach is challenging in practice because it relies on an accurate characterization of all system parameters and back-action evading measurements. Moreover, a complete reconstruction, especially in the case of pure, entangled quantum states, is complicated by effects of finite measurement statistics, as we will show in the following. To date, it is still an open task to verify experimentally stationary optomechanical entanglement.

This work proposes an alternative approach that avoids a complete quantum state reconstruction. It is based on an argument that allows to infer optomechanical entanglement from the observation of entanglement between successive, nonoverlapping light modes. Such an inference is possible under the assumption that the temporal modes of the light and the mechanical oscillator were not correlated initially, i.e., before the optomechanical interaction. The argument is analogous—and in fact generalizes—the one in the demonstration of pulsed optomechanical entanglement [14,18]. The first aspect of our work presents and proves this central argument.

The second aspect of this work describes a scheme to demonstrate experimentally stationary optomechanical

*These authors contributed equally to this work.

†Present address: Department of Microtechnology and Nanoscience (MC2), Chalmers University of Technology, Kemivägen 9, Göteborg, Sweden.

‡Present address: QuTech, Delft University of Technology, Lorentzweg 1, 2628 CJ Delft, The Netherlands.

Published by the American Physical Society under the terms of the [Creative Commons Attribution 4.0 International license](https://creativecommons.org/licenses/by/4.0/). Further distribution of this work must maintain attribution to the author(s) and the published article's title, journal citation, and DOI.

entanglement, making use of the argument. The scheme applies to cavity optomechanical systems with large mechanical quality factor and large cavity linewidth as compared to the mechanical frequency (sideband unresolved regime). The systems must be in their steady state and driven by a continuous laser that is resonant with the cavity. Importantly, the drive is strictly constant (no modulations). The scheme is based on the measurement of an entanglement witness on suitably chosen temporally ordered modes of the light escaping the cavity—the argument allows us to infer optomechanical entanglement from witnessing entangled light modes. If the dynamics are stationary, the state is invariant under translation in time—and so is the entanglement. We emphasize that the time-ordered light modes can be extracted from measured data in postprocessing. The formulation of this scheme is simple enough that we could study it analytically and prove that it detects entanglement in the form of squeezing of Einstein-Podolski-Rosen (EPR) modes of light or suitable generalizations thereof. We predict EPR squeezing to scale inversely proportional to the quantum cooperativity (Ref. [23] had found a similar behavior) and asymptotically reach 50% of noise reduction below the shot noise level. This leaves a safe margin for experimental imperfections, such as finite detection efficiency. As in Ref. [23], we find that optomechanical entanglement persists even for a quantum cooperativity below unity, albeit only to a small extent.

The operating regime of the scheme we propose corresponds to the generic configuration of an optomechanical position or force sensor. In a continuous position sensor the measured object (the mechanical oscillator) and the measurement apparatus (the light field) share entanglement. This is the central idea of the quantum mechanical measurement theory [24–26]: The process underlying a physical measurement is ultimately an entangling interaction between object and the measuring apparatus (observer). This applies regardless of whether the measurement is performed at high quantum cooperativity, for which it is limited by measurement back-action, or at low cooperativity, where it is limited by shot noise or thermal noise. Under normal conditions, it is virtually impossible to detect the entanglement between object and apparatus as it usually involves an uncontrollable variety of environmental degrees of freedom due to the amplification associated with the measurement. It is intriguing to see that with an optical-mechanical sensor it is possible to capture this entanglement in a feasible measurement and thus shift the Heisenberg–von Neumann cut between object and observer.

This article is organized as follows: In Sec. II we introduce necessary elements of optomechanics. Our argument and scheme to detect optomechanical entanglement are developed in Sec. III. We present our results and predictions regarding detectable signatures of optomechanical entanglement in Sec. IV.

II. ELEMENTS OF OPTOMECHANICS

This section describes, concisely, the linearized cavity optomechanical model we rely on in the following. It is a well-studied theory and many experiments demonstrated that it describes accurately diverse optomechanical devices

operating in a wide range of parameter regimes; see the review on optomechanics [27] for a thorough presentation.

We consider a standard optomechanical system [27] comprising a single mechanical (oscillatory) mode interacting with a single light mode of a cavity. Mechanical and light fields are bosonic, described by two pairs of dimensionless Hermitian operators, $x_m(p_m)$ and $x_c(p_c)$, referred to as position (momentum) and amplitude (phase) quadratures of the mechanical and cavity mode, respectively. These operators obey equal-time canonical commutation relations,

$$[x_\alpha(t), p_\beta(t)] = i\delta_{\alpha,\beta}, \quad (1)$$

where $\alpha, \beta = m, c$ and $\delta_{\alpha,\beta}$ is the Kronecker delta symbol. Throughout this work $\hbar = 1$. We will also use ladder operators a_α and a_α^\dagger defined by

$$a_\alpha := (x_\alpha + ip_\alpha)/\sqrt{2} \quad (2)$$

obeying $[a_\alpha(t), a_\beta^\dagger(t)] = \delta_{\alpha,\beta}$.

In a frame rotating at the frequency ω_d of the field driving the optomechanical cavity, the Hamiltonian of the linearized dynamics is given by [27]

$$H = \omega_m a_m^\dagger a_m - \delta a_c^\dagger a_c + g(a_m^\dagger a_c^\dagger + a_m a_c^\dagger + \text{H.c.}). \quad (3)$$

We denote the oscillation frequency of the mechanics by ω_m , $\delta \approx \omega_d - \omega_c$ is the detuning of the drive from cavity resonance, and g is the coupling strength (depending on the drive power). The interaction contains two processes that create sidebands in the cavity field: the down-conversion of a phonon and a photon at a lower energy than the drive (that is, Stokes scattering to sideband frequency $-\omega_m$) and the state-swap of a phonon onto a photon at higher energy than the drive (that is, anti-Stokes scattering to sideband frequency $+\omega_m$).

For completeness (this is a technical note), we mention here that the nonlinear optomechanical Hamiltonian can be written in terms of a Kerr interaction in the cavity [28,29]. Subsequent linearization gives a single-mode (degenerate) down-conversion interaction term: $[a_c^2 + (a_c^\dagger)^2]g^2/\omega_m$. It is possible to show that such a process is not sufficient to generate the entanglement we propose to reveal with our scheme (described in the coming Sec. III). To do so, apply the mode functions Eq. (23) to the two-time correlators of a degenerate parametric down-converter [[30], ch. 10] and evaluate the integrals—this is an application of the formalism developed in Appendix B—then check that our entanglement criterion Eq. (21) is never violated this way. Therefore, the linearized model (3) is the relevant one for our purpose.

The cavity mode is coupled to the free electromagnetic field outside the cavity. The ladder operators describing this one-dimensional field, $a_{\text{in}}(t)$ and $a_{\text{in}}^\dagger(t)$, have the following Markovian correlation functions:

$$\langle a_{\text{in}}(t) \rangle = 0, \quad \langle a_{\text{in}}^\dagger(t) \rangle = 0, \quad (4a)$$

$$\langle a_{\text{in}}^\dagger(t) a_{\text{in}}(t') \rangle = 0, \quad \langle a_{\text{in}}(t) a_{\text{in}}^\dagger(t') \rangle = \delta(t - t'). \quad (4b)$$

We neglect here thermal occupation numbers for optical frequencies.

The thermal bath of the mechanical oscillator is modeled by quantum Brownian motion damping with the Hermitian

noise operator ξ [30,31]. At high temperatures of the mechanical bath $n_{\text{th}} \approx k_{\text{B}}T_{\text{bath}}/\hbar\omega_{\text{m}} \gg 1$ and/or large mechanical quality factor $Q = \omega_{\text{m}}/\gamma_{\text{m}} \gg 1$ its correlators are approximately Markovian, reflected by

$$\langle \xi(t) \rangle = 0, \quad (5a)$$

$$\langle \xi(t)\xi(t') + \xi(t')\xi(t) \rangle \approx (2n_{\text{th}} + 1)\delta(t - t'). \quad (5b)$$

Including cavity (power) decay at rate κ and viscous damping of the oscillator at rate γ_{m} , the open-system dynamics is described by the quantum Langevin equations (QLE) [27,32]

$$\dot{x}_{\text{m}} = \omega_{\text{m}}p_{\text{m}}, \quad (6a)$$

$$\dot{p}_{\text{m}} = -\gamma_{\text{m}}p_{\text{m}} - \omega_{\text{m}}x_{\text{m}} - 2gx_{\text{c}} + \sqrt{2\gamma_{\text{m}}}\xi, \quad (6b)$$

$$\dot{x}_{\text{c}} = -\delta p_{\text{c}} - \frac{\kappa}{2}x_{\text{c}} + \sqrt{\kappa}x_{\text{in}}, \quad (6c)$$

$$\dot{p}_{\text{c}} = \delta x_{\text{c}} - \frac{\kappa}{2}p_{\text{c}} - 2gx_{\text{m}} + \sqrt{\kappa}p_{\text{in}}. \quad (6d)$$

In the following, we consider the special case of a resonantly driven cavity, $\delta = 0$, which corresponds to the standard configuration of an optomechanical position or force sensor. The generalization to nonzero detuning is straightforward but results in significantly more involved analytical expressions that we will not reproduce here. In Eqs. (6), x_{in} and p_{in} correspond to shot noise because we work in a suitably displaced frame where mean amplitudes were shifted to zero, see Ref. [27] for details.

Our study always assumes stable dynamics such that the steady state is reached eventually [33]. Equations (6) can be solved easily in Fourier space [16]; see Appendix B 1 for the Fourier transform conventions we have adopted. The quadratures of the light emitted by the cavity are given by input-output relations [34] and take the form

$$x_{\text{out}}(\omega) = \mathcal{S}(\omega)x_{\text{in}}(\omega), \quad (7a)$$

$$p_{\text{out}}(\omega) = \mathcal{S}(\omega)p_{\text{in}}(\omega) + 4g^2\chi_{\text{opt}}^2(\omega)\chi_{\text{m}}(\omega)x_{\text{in}}(\omega) - 2g\sqrt{2\gamma_{\text{m}}}\chi_{\text{opt}}(\omega)\chi_{\text{m}}(\omega)\xi(\omega). \quad (7b)$$

We have introduced here the mechanical and the optical susceptibilities

$$\chi_{\text{m}}(\omega) := \frac{\omega_{\text{m}}}{\omega_{\text{m}}^2 - \omega^2 - i\omega\gamma_{\text{m}}}, \quad (8)$$

$$\chi_{\text{opt}}(\omega) := \frac{\sqrt{\kappa}}{\frac{\kappa}{2} - i\omega}, \quad (9)$$

and the reflection phase

$$\mathcal{S}(\omega) := \frac{\frac{\kappa}{2} + i\omega}{\frac{\kappa}{2} - i\omega}. \quad (10)$$

We assume $Q = \omega_{\text{m}}/\gamma_{\text{m}} \gg 1$, which is a typical feature in micro-optomechanical setups. This allows us to approximate the poles of the mechanical susceptibility, Eq. (8), by $\omega_{\pm} \approx \pm\omega_{\text{m}} - i\gamma_{\text{m}}/2$, such that

$$\chi_{\text{m}}(\omega) \approx \frac{1}{2} \left(\frac{1}{\omega - \omega_{-}} - \frac{1}{\omega - \omega_{+}} \right), \quad (11a)$$

$$|\chi_{\text{m}}(\omega)|^2 \approx \frac{1}{4} \left(\frac{1}{|\omega - \omega_{-}|^2} + \frac{1}{|\omega - \omega_{+}|^2} \right). \quad (11b)$$

Both are strongly peaked at $\pm\omega_{\text{m}}$. Close to these frequencies and in the sideband unresolved regime ($\kappa \gg \omega_{\text{m}}$) we approximate Eqs. (9) and (10) by, respectively,

$$\chi_{\text{opt}}(\omega) \approx \frac{2}{\sqrt{\kappa}}, \quad \mathcal{S}(\omega) \approx 1. \quad (11c)$$

In the limit of these approximations, the characteristic response time $1/\kappa$ of the intracavity field is the shortest timescale of the system, such that the intracavity field is adiabatically eliminated from the dynamics. In other words, the mechanical oscillator is effectively directly coupled to the output field, without any spectral filtering due to the cavity, cf. Eq. (11c). In this limit, one can rewrite Eq. (7b) as

$$p_{\text{out}}(\omega) = \mathcal{S}(\omega)p_{\text{in}}(\omega) + 4\Gamma_{\text{ro}}\chi_{\text{m}}(\omega)x_{\text{in}}(\omega) - 2\sqrt{2\gamma_{\text{m}}}\Gamma_{\text{ro}}\chi_{\text{m}}(\omega)\xi(\omega), \quad (12)$$

where we have defined the readout rate

$$\Gamma_{\text{ro}} := \frac{4g^2}{\kappa}. \quad (13)$$

The first term of p_{out} in Eq. (12) is the contribution of shot noise reflected by the cavity. The second term is the contribution from shot noise driving the mechanical motion and being transferred back to the light via the interaction—this effect is called *back-action*. The last term is the contribution of the thermal fluctuations from the mechanical bath, mapped onto the light via the optomechanical interaction. In the context of position or force sensing, this term constitutes the signal to be determined from a measurement of the phase quadrature p_{out} . The relative size of the readout term to the thermal noise in Eq. (12) is the so-called quantum cooperativity,

$$\mathcal{C}_{\text{q}} := \frac{4g^2}{\kappa\gamma_{\text{m}}(n_{\text{th}} + 1)} \approx \frac{\Gamma_{\text{ro}}}{\Gamma_{\text{th}}}. \quad (14)$$

The last approximation holds in the high-temperature limit, and we defined the thermal decoherence rate of the mechanical oscillator,

$$\Gamma_{\text{th}} := \gamma_{\text{m}}(n_{\text{th}} + 1/2), \quad (15)$$

which sets the scale of the thermal force in Eq. (6b).

At a fundamental level, the transduction of information on position or force is associated with the generation of correlations, or even quantum entanglement, between the observed object (here the mechanical oscillator) and the measurement apparatus (the light field). In the next section we will explain how stationary optomechanical entanglement can be proven unambiguously based solely on measurements of the light field.

III. VERIFICATION OF OPTOMECHANICAL ENTANGLEMENT

A. Inference of optomechanical entanglement from measurement of light

The continuous traveling light field entering and escaping an optomechanical cavity can be decomposed into pulses, i.e., a sequence of nonoverlapping temporal modes. A temporal mode labeled i is defined by a mode function f_i , see Fig. 1(a). We restrict ourselves to two consecutive modes of such a




FIG. 1. (a) The continuous light field (traveling to the left because the time axis points to the right) can be decomposed (abstractly) into temporal modes via an abstract modulation by mode functions f_i . The shaded area is a temporal separation between the modes. (b) Two temporal modes are considered: an early pulse (E) and a late pulse (L) defined by the mode functions f_E and f_L . (c) The quantum circuit corresponding to the dynamics. The mechanical oscillator (M); the early and the late pulses are initially in an uncorrelated state. M interacts sequentially with E and then L according to the quantum channels \mathcal{E}_{EM} and \mathcal{E}_{ML} , respectively.

decomposition: an early pulse (E) and a late pulse (L). They have support on time intervals $[t_E - \tau, t_E]$ and $[t_L, t_L + \tau]$, respectively, with $t_E < t_L$, $T_{sep} := t_L - t_E$ their separation, and $\tau > 0$ their duration, see Fig. 1(b). In this picture, the mechanical oscillator (M) interacts first with the early pulse, according to a quantum channel (i.e., a completely positive map) \mathcal{E}_{EM} , and then with the late pulse, according to \mathcal{E}_{ML} . This temporal ordering of the dynamics is illustrated by the quantum circuit in Fig. 1(c). We assume that the two pulses and the mechanical oscillator are initially in a product state ρ_{EML}^{init} . The final state of the three systems is $\rho_{EML}^{fin} = (\mathbb{1}_E \otimes \mathcal{E}_{ML})(\mathcal{E}_{EM} \otimes \mathbb{1}_L)\rho_{EML}^{init}$. If the reduced state of the mechanical oscillator and the early pulse after the first channel $\rho_{EM} = \text{tr}_L(\mathcal{E}_{EM}\rho_{EML}^{init})$ is separable, then the final state of early and late pulses $\rho_{EL} = \text{tr}_M(\rho_{EML}^{fin})$ is separable, too. Conversely, if ρ_{EL} is entangled, then ρ_{EM} must have been entangled. Thus, the measurement of entanglement between early and late pulses implies optomechanical entanglement. A detailed proof of this intuitive but nontrivial statement is presented in Appendix A.

Based on this reasoning, entanglement between a mechanical resonator and a traveling wave pulse of a microwave field had been demonstrated in Ref. [14], as outlined in Ref. [18]. Optomechanical entanglement had been deduced from the

measurement of entanglement between two consecutive microwave pulses that originated from sequential interactions with the mechanical oscillator. In the scheme of Refs. [14,18], the two processes \mathcal{E}_{EM} and \mathcal{E}_{ML} are different in nature and constructed to optimize entanglement generation in \mathcal{E}_{EM} and state readout during \mathcal{E}_{ML} . This requires, in particular, to work in the resolved-sideband limit ($\kappa/\omega_m < 1$) and to set the driving field blue detuned ($\delta = \omega_m$) in the first (E-M) interaction and red detuned ($\delta = -\omega_m$) during the second (M-L) interaction. In both processes the applied fields are pulsed and steer the optomechanical system through nonstationary, nonequilibrium states.

Our argument, at the beginning of this section, has two premises that the system must fulfill: time ordering of the interactions and no initial correlations. In principle, no additional knowledge about the system is needed to use the argument to relate the presence of entanglement in the light to the presence of optomechanical entanglement. The argument makes a sufficient inference: If the temporal modes are entangled, then there is optomechanical entanglement; if they are not, then no conclusion can be drawn. This is in contrast with the method proposed in Refs. [19–21] that can characterize completely the optomechanical entanglement (full state tomography), based on extended and precise knowledge about the system. The trade-off between both methods is the amount of knowledge about the system necessary to obtain information about the oscillator. In this sense, both approaches are complementary.

The requirement that the three parties involved are initially uncorrelated excludes the hypothetical scenario of Refs. [35–39]. There entanglement is distributed via a mediator, without the mediator ever becoming entangled (see end of Appendix A for details). Since in real experiments the light might contain some degree of classical correlations, demonstrating entanglement between certain modes of light that were mediated by a mechanical oscillator [6,7] does not allow us to make unambiguous statements regarding genuine optomechanical entanglement.

Light in the cavity has a lifetime (of the order $1/\kappa$) that effectively delays the propagation of an incoming pulse. To guarantee the strictly sequential interaction depicted in Fig. 1(c), the temporal separation T_{sep} between the early and late pulses must be larger than $1/\kappa$, so that the pulses interact with the mechanics one after the other. In this work, we will focus on the regime where $1/\kappa$ is the shortest timescale; this choice will be motivated (physically) in Sec. III C by our choice of mode functions f_E and f_L . However, in principle, it is not excluded that optomechanical entanglement can be demonstrated in systems with relatively narrow linewidth cavities.

In the following, we will use the logic of the argument presented above to show that optomechanical entanglement can be verified in the regime of continuous driving of an optomechanical cavity by a constant laser with fixed detuning, such that the mechanical oscillator and the output field of the cavity are in a stationary state. The two successive temporal pulses are extracted in postprocessing from the continuous measurement on the output field. Because the overall state of the mechanical oscillator and the output field is stationary, it does not matter which intervals $[t_E - \tau, t_E]$ and $[t_L, t_L + \tau]$ are

extracted from the stationary homodyne current: Any of its properties, such as entanglement of early and late pulses, will depend only on the pulse length τ and separation T_{sep} between the pulses but not on the particular instants of time t_E and t_L . Formally, we define annihilation operators corresponding to these temporally ordered modes by

$$r_E := \int_{t_E-\tau}^{t_E} dt f_E(t) a_{\text{out}}(t), \quad (16a)$$

$$r_L := \int_{t_L}^{t_L+\tau} dt f_L(t) a_{\text{out}}(t), \quad (16b)$$

where $f_E(t)$ and $f_L(t)$ are the temporal mode functions of the early and late modes, respectively. The properties of a_{out} are determined by Eqs. (7), which describe the stationary state of light in conjunction with the properties of the ongoing noise processes Eqs. (4) and (5). Because the two modes E and L are ordered in time and interact sequentially with the mechanical oscillator, the scenario of Fig. 1(c) applies. Before the interaction with the mechanics, modes E and L are defined with respect to a_{in} in Eq. (16) (distinct modes of shot noise in our displaced frame), hence they are not correlated to the oscillator nor to each other. Therefore the argument applies and optomechanical entanglement is demonstrated through observing that the two light modes share entanglement.

It is instructive to compare this once again to the pulsed scheme of Refs. [14,18]. There the properties of early and late pulses had to be inferred from an integration in time of the respective equations of motion, Eqs. (6), with different detuning $\delta = \pm\omega_m$ for E and L. Here we can infer all properties of E and L from the stationary solutions, Eqs. (7), for a fixed detuning. In the pulsed scheme the description of the three modes E, L, and M was essentially complete in the sense that the dynamics were designed so that no correlations to any other mode of the light field were established. Here the restriction to the two pulses E and L is a massive simplification: In reality, the mechanical oscillator will exhibit correlations to more modes than E and L, and the stationary light field will exhibit a large variety of internal correlations, e.g., in the form of ponderomotive squeezing. Still, for demonstrating stationary entanglement of the mechanical oscillator and light, it is sufficient to consider the three modes E, M, and L.

For the following discussion it will be mathematically convenient to formally allow for infinitely extended pulses, corresponding to $\tau \rightarrow \infty$, whose pulse envelopes $f_{E/L}(t)$ tend to zero for $t \rightarrow \mp\infty$, respectively (keeping the mode finite does not change the derivation). The characteristic scale at which the envelopes tend to zero defines an effective pulse length. Furthermore, because of stationarity, we can set arbitrarily t_E to $-T_{\text{sep}}/2$ and t_L to $T_{\text{sep}}/2$ without loss of generality. We write the mode operators r_i , for $i = E, L$, as

$$r_i = \int_{-\infty}^{\infty} dt f_i(t) a_{\text{out}}(t) \quad (17)$$

where $f_E(t)$ has to be an anticausal function with respect to $-T_{\text{sep}}/2$ [i.e., $f_E(t) = 0$ for $t > -T_{\text{sep}}/2$] and $f_L(t)$ has to be causal with respect to $T_{\text{sep}}/2$ [i.e., $f_L(t) = 0$ for $t < T_{\text{sep}}/2$]. The r_i must fulfill bosonic commutation relations, $[r_i(t), r_j^\dagger(t)] = \delta_{i,j}$, which correspond to an orthonormaliza-

tion constraint for the mode functions

$$\int_{-\infty}^{\infty} dt f_i(t) f_j^*(t) \stackrel{!}{=} \delta_{i,j}; \quad i, j = E, L. \quad (18)$$

With Eq. (2) we obtain the quadrature operators x_i, p_i of the early and late modes of the output field.

In order to prove stationary optomechanical entanglement, we need to identify suitable mode functions and system parameters that result in an entangled state ρ_{EL} of early and late pulses, which can be verified from a measurement of the output light field of the optomechanical cavity.

In Sec. III B we motivate a choice of entanglement criterion. This choice specifies what information the measurement procedure must retrieve from the output field. In Sec. III C we motivate a particular class of temporal mode functions to process measurement data. This choice is based on our understanding of the stationary optomechanical dynamics and leads to choosing the particular parameter regime of unresolved sidebands and undetuned drive. These choices determine an implementable experimental scheme that we can study analytically; the results of the study are presented in Sec. IV.

B. Entanglement criteria

We note first that the optomechanical dynamics is linear and the driving fields correspond to Gaussian white noise. This implies that the stationary state of the optomechanical system and the output field is Gaussian and that the state of the two temporal modes in the output field, introduced in Eq. (17), is Gaussian, too. First moments and covariances of canonical operators x_i, p_i ($i = E, L$) determine Gaussian states completely. As a consequence all entanglement properties are fully determined by the latter. Entanglement of the two-mode Gaussian state of E and L can be quantified by means of suitable entanglement measures [40–42] (such as the Gaussian entanglement of formation [43] or the logarithmic negativity [44–46]), which can be calculated from the experimentally accessible covariances of the state ρ_{EL} . Moreover, such entanglement measures often provide bounds to non-Gaussian states for given covariances.

In order to proceed in a fully systematic way, one could try to optimize temporal mode functions in Eq. (17) with respect to an entanglement measure and other system parameters (such as optomechanical coupling g , etc.), as in Ref. [23]. However, due to the highly nonlinear dependence of entanglement measures on the state ρ_{EL} such an optimization seems too challenging. Moreover, our argument that relates entanglement in the light field to optomechanical entanglement (presented at the beginning of Sec. III A) is a sufficient condition for entanglement and, on its own, does not allow to relate the amount of entanglement (characterized by a measure) shared by the light modes to the amount of entanglement between the oscillator and the light.

Instead, we use entanglement criteria that are linear in covariances, i.e., second moments of quadratures [47–49]. Geometrically, these criteria specify separating hyperplanes from the convex set of covariances that are compatible with separable Gaussian states [49]. On the level of covariances, the geometry is that of an entanglement witness for quantum

states. Since each test is linear in the covariances, each test defines an implementable and feasible measurement procedure. What is more, one can argue that a strong violation of such criteria is accompanied by a quantitative statement, in that several entanglement measures are lower bounded by quantitative violations of such entanglement tests [49–52]. Moreover, we will use in Sec. IV that, for an anticipated covariance, one can efficiently find the optimal test that best certifies the entanglement present in a Gaussian state [49].

For our analytical consideration we will resort to a special case of such criteria, referred to as Duan’s criterion [47]: the so-called EPR variance (Δ_{EPR}),

$$\Delta_{\text{EPR}} := \Delta(x_E + x_L^\phi) + \Delta(p_E - p_L^\phi), \quad (19)$$

where

$$\begin{aligned} x_L^\phi &= x_L \cos \phi + p_L \sin \phi, \\ p_L^\phi &= p_L \cos \phi - x_L \sin \phi. \end{aligned}$$

Our notation for the variances is

$$\Delta A := \langle A^2 \rangle_{\rho_{\text{EL}}^{\text{init}}} - \langle A \rangle_{\rho_{\text{EL}}^{\text{init}}}^2, \quad (20)$$

where the expectation values are taken with respect to the initial density operator $\rho_{\text{EL}}^{\text{init}} = |0\rangle\langle 0|_{\text{E}} \otimes |0\rangle\langle 0|_{\text{L}}$ (in our displaced frame). Δ_{EPR} quantifies the simultaneous correlations between pairs of quadratures of *different modes*. For two-mode Gaussian states,

$$\Delta_{\text{EPR}} < 2 \quad (21)$$

implies (only sufficient) that the state is entangled. In phase space, this corresponds to a reduction of the Gaussian state’s variance (uncertainty) below the variance of a two-mode vacuum state (the coherent state that corresponds to the shot noise of the temporal modes) along a particular direction in the plane $(x_E + x_L^\phi)$ and $(p_E - p_L^\phi)$: This is a particular form of two-mode-squeezing that we call EPR squeezing. In terms of ladder operators, the EPR variance can be written as

$$\begin{aligned} \Delta_{\text{EPR}} &= \langle r_E r_E^\dagger + r_E^\dagger r_E + r_L r_L^\dagger + r_L^\dagger r_L \rangle \\ &+ (e^{i\phi} \langle r_L r_E + r_E r_L \rangle + \text{H.c.}). \end{aligned} \quad (22)$$

This relation can be readily evaluated from a record of homodyne measurements, along with appropriate postprocessing in order to extract adequate (anti-)causal temporal modes. Again, the Duan criterion is in general not an optimal test but can be optimized for a given Gaussian state.

C. Temporal modes

In this section we address the question of how to choose the mode functions $f_{\text{E/L}}$ in Eq. (17) in order to achieve largest violation of the separability bound Eq. (21). The EPR variance can be expressed as a quadratic form of the mode functions, which we show explicitly in Appendix B, cf. Eq. (B8). Unfortunately the minimization does not map to a simple eigenvalue problem due to the required (anti-)causality and normalization of the mode functions.

We therefore proceed by choosing a suitable variational class of mode functions that we motivate as follows: In Sec. II, we explained that the optomechanical unitary dynamics produce sidebands around the driving frequency at




FIG. 2. Mode functions of Eqs. (23): They are temporally ordered and nonoverlapping as required by the entanglement verification argument of Sec. III A. They are orthonormal as required by Eq. (18). And they are pulses to account for decoherence. The early pulse (in red) has a raising exponential time envelope and is resonant with the red sideband at $-\omega_m$. The late pulse (in blue) has an exponentially decaying envelope in time and is resonant with the blue sideband at $+\omega_m$.

$\pm\omega_m$ (in the frame rotating at the drive’s frequency). The lower (red) sideband is produced by the down-conversion part (also termed two-mode-squeezing) of the interaction and it is known to produce EPR-like entanglement [16,18]: This sideband is entangled with the mechanics. The upper (blue) sideband is produced by the beam-splitter contribution of the interaction and corresponds to a coherent state swap of the mechanical and cavity fields (preserving quantum correlations with the red sideband): This sideband encodes the state of the mechanics, which was entangled with the red sideband some moments before. The blue sideband is thus entangled with the light in the red sideband at previous times. If $\delta = 0$ and if the cavity linewidth κ is not much narrower than ω_m , then both sidebands will have significant spectral components in the measured output—this is the reason for choosing the regime of unresolved sidebands and resonant drive. We choose early and late mode functions that capture the temporal order of these processes: The early mode extracts information from the red sideband and the late mode from the blue sideband. This is done with a demodulation of the detected signal by $e^{\pm i\omega_m t}$, which makes the corresponding spectral component resonant.

We expect the quantum correlations at different points in time to decrease with the duration separating them. This is because the incoherent coupling to the mechanical bath eventually destroys coherent correlations between mechanics and light. We therefore opt for pulses with an effective duration that is smaller than the thermal decoherence time Γ_{th}^{-1} , cf. Eq. (15). As a variational class of mode functions we choose exponentially decaying envelopes for the demodulating phases, see Fig. 2,

$$f_E(t) := N e^{(\Gamma - i\omega_m)t} \theta(-t - T_{\text{sep}}/2), \quad (23a)$$

$$f_L(t) := N e^{(-\Gamma + i\omega_m)t} \theta(t - T_{\text{sep}}/2), \quad (23b)$$

where the decay rate Γ scales the effective duration of the mode, θ is the Heaviside step function and $N = (2\Gamma e^{\Gamma T_{\text{sep}}})^{1/2}$ is the normalization constant. This class of mode functions is in particular motivated by Ref. [23], where it is shown that the temporal mode of the light sharing maximal amount of entanglement (largest negativities) with the oscillator have an exponentially decaying envelope for a demodulating phase




FIG. 3. Summary of the scheme we propose: Consider a mechanical resonator that is well isolated from its thermal bath ($\omega_m \gg \gamma_m$), in a cavity not resolving sidebands ($\kappa \gg \omega_m$), and driven in its steady state by a constant-continuous and resonant ($\delta = 0$) laser (x_{in}, p_{in}). The output field (x_{out}, p_{out}) is continuously monitored, e.g., by homodyning. The corresponding measurement record is overlapped with appropriate mode functions $f_{E/L}$ [Eqs. (17)] to yield the ladder operators of the temporal modes ($r_{E/L}, r_{E/L}^\dagger$). Entanglement is tested with the EPR variance Eq. (22).

at the mechanical frequency ω_m . These mode functions are anticausal and causal, respectively, and they are orthonormal by construction. The pulse decay rate Γ is a free variational parameter with respect to which we will minimize Δ_{EPR} .

D. Experimental task

Section III defines a readily implementable scheme to detect optomechanical entanglement between temporally ordered modes of the output field. The optomechanical cavity is driven on resonance in the non-sideband-resolved regime by a constant input laser while the cavity output field is continuously monitored. The choice of the exact measurement scheme depends on the entanglement criterion of interest. Here Eq. (19) [or equivalently Eq. (22)] prescribes what information the detection scheme in an experiment must provide. For example, the equal-time correlators in Eq. (19) can be evaluated from records of two homodyne measurements of the phase and the amplitude of the output field. From such a record, temporally ordered modes can be extracted according to Eq. (17). If the dynamics are stationary, the detection of entanglement between the light modes implies that the mechanical oscillator and the output light share stationary entanglement. Figure 3 summarizes this procedure.

IV. RESULTS

This section has two parts: First, we provide an approximate formula for the EPR variance and comment on what it teaches us about entanglement in the system; second, we benchmark the approximate formula with its exact counterpart. The latter is very cumbersome in its symbolic form and, on its own, provides only numerical results, whereas our approximate formula gives generic behavior with respect to the parameters.

A. Approximate formula for the EPR variance

Using the mode functions of Eqs. (23) in the definition of the mode operators in Eq. (17), the EPR variance in Eq. (22) can be evaluated by means of the input-output relations Eqs. (7) and the noise correlators Eqs. (5) and (4). A detailed derivation is given in Appendix B.

Here we give the final result, which is compared to (and backed up by) exact numerical calculations in Sec. IV B,

$$\Delta_{EPR} = 2 + \eta \frac{4\Gamma_{ro}}{\Gamma + \frac{\gamma_m}{2}} \left[\frac{2(\Gamma_{ro} + \Gamma_{th})}{\gamma_m} \left(1 - \frac{\Gamma e^{-\gamma_m T_{sep}/2}}{\Gamma + \frac{\gamma_m}{2}} \cos \phi \right) - \left(\frac{\Gamma e^{-\gamma_m T_{sep}/2}}{\Gamma + \frac{\gamma_m}{2}} \cos \phi \right) \right]. \quad (24)$$

The readout and thermal decoherence rate, Γ_{ro} and Γ_{th} , have been defined in Eqs. (13) and (15). We included a finite detection efficiency $\eta \leq 1$. Equation (24) is derived for a resonant drive $\delta = 0$ and the regime $\kappa \gg \omega_m \gg \gamma_m$ such that approximations Eqs. (11) apply. Furthermore, in order to arrive at an analytically tractable formula, we made the technical assumption that the pulse envelopes decay at a rate Γ fulfilling

$$\Gamma \ll \frac{\omega_m}{\sqrt{n_{th}(\mathcal{C}_q + 1)}} \approx \frac{\omega_m}{\sqrt{\mathcal{C}_{cl} + n_{th}}}. \quad (25)$$

Here \mathcal{C}_q is the optomechanical quantum cooperativity, cf. Eq. (14), and $\mathcal{C}_{cl} := 4g^2/\kappa\gamma_m$ is the classical cooperativity. The approximation assumes the large-temperature limit. Equation (25) has to be read as a limitation on the optomechanical coupling g . As we will see, for couplings that violate Eq. (25) the EPR variance is not a suitable entanglement criterion anymore. Thus, in the regime in which the EPR variance is of interest, Eq. (25) is a self-consistent restriction.

It is useful to characterize the circumstances for which Δ_{EPR} is minimal, so that the violation of the separability bound, Eq. (21), is least susceptible to inevitable experimental imperfections. To this end, we set $\phi = 0$ in Eq. (24). The first term in the square brackets is always positive and monotonically decreasing with the decay rate of the temporal modes Γ . The second term is negative and monotonically increasing with Γ . Only if the second term can compensate the first one is it possible to detect entanglement. In view of this and the overall scaling in front of the square brackets with respect to Γ , it is clear that there is an optimal pulse bandwidth yielding an optimal EPR variance.

We discuss first the result of this minimization for ideal detection, $\eta = 1$, and vanishing pulse separation, that is, in the zeroth order of $\gamma_m T_{sep}$. A straightforward calculation gives the

optimal pulse bandwidth

$$\begin{aligned}\Gamma_{\text{opt}} &= 2(\Gamma_{\text{ro}} + \Gamma_{\text{th}}) + \frac{\gamma_m}{2} \\ &\approx 2\gamma_m(\mathcal{C}_{\text{cl}} + n_{\text{th}}),\end{aligned}\quad (26)$$

for which the approximation holds when $n_{\text{th}} \gg 1$. We expected that the pulses have to decay faster than the thermal decoherence rate in order to preserve the coherence between the pulses with large probability. This means that the pulses' bandwidth cannot be too narrow. The factor of 2 accounts for the fact that the coherence must be kept across both pulses, i.e., there may be no significant incoherent leakage over times $\sim 2/\Gamma_{\text{opt}}$. Increasing the readout rate (or the cooperativity) leads to shorter optimal pulses. We interpret this tendency as a tentative to extract information from the output light as fast as the dynamics allows, in order to minimize the chances of decoherence. This seems a natural strategy because, in our model, thermal decoherence is the only channel through which entanglement can be lost. However, this might not be the best strategy in a real experiment: as pulses become shorter, their bandwidth broadens and incoherent spectral features from technical noise and/or additional mechanical modes will be resolved by the pulses. We expect that this will prevent observation of entanglement if not accounted and controlled carefully [53]. Moreover, the form of the optimal bandwidth Γ_{opt} is only valid when Eq. (25) holds, which limits the maximal bandwidths we can predict this way. The optimal pulse bandwidth in Eq. (26) is compatible with the assumption in Eq. (25), if $2(\mathcal{C}_{\text{cl}} + n_{\text{th}})^{3/2} \ll Q$. For large optomechanical coupling g , which violate this condition, entanglement will not be detectable in the form of EPR squeezing and one should instead consider more general entanglement witnesses, as we will see.

Formula (24), for the optimal choice of bandwidth Γ_{opt} , predicts

$$\Delta_{\text{EPR}} = 1 + \frac{1}{\mathcal{C}_q + 1}. \quad (27)$$

For arbitrarily small (but finite) cooperativities, this expression is always smaller than two. This means that entanglement between the light modes is always present and so is optomechanical entanglement. This finding is consistent with the results of Ref. [23], where this surprising fact has been noted first. Equation (27) constitutes the main result of our work. For large quantum cooperativity Δ_{EPR} approaches 50% of squeezing below shot noise. This limit hints at the fact that we consider only two (out of infinitely many) light modes that encode correlations with the mechanics.

When finite detection efficiency and pulse separation are taken into account, the minimal EPR variance, Eq. (27), is modified as follows (to first order in $\gamma_m T_{\text{sep}}$):

$$\Delta_{\text{EPR}} = 2 - \eta \frac{\mathcal{C}_q}{\mathcal{C}_q + 1} + 4\eta\Gamma_{\text{ro}}T_{\text{sep}}. \quad (28)$$

In the relevant regime of large cooperativity, $\mathcal{C}_q > 1$, we have $\Gamma_{\text{ro}} > \Gamma_{\text{th}}$ such that the pulse separation T_{sep} needs to stay well below the thermal decoherence time Γ_{th}^{-1} , as one would expect.

From the derivation detailed in Appendix B, it is possible to give a detailed account on the physical origin of each term in Eq. (24). The factor 2 at the front is the shot noise contribution of the light field that we would observe in the absence of optomechanical coupling (i.e., if $\Gamma_{\text{ro}} = 0$). The first term in the square brackets is due to autocorrelations in thermal noise and in back-action noise, contributing to the two pulses. This term has two parts: a nonnegative part coming from intrapulse correlation in each of the two temporal modes (early or late with themselves) and a negative part coming from the interpulse correlation between early and late mode. The net effect of both parts is always positive, therefore autocorrelations in thermal noise and back-action noise do not contribute to entanglement. The last term in the square brackets corresponds to cross-correlations of shot noise and back-action noise. These correlations are also at the basis of ponderomotive squeezing typically observed in the frequency domain [4,5]. Here the correlations refer purely to interpulse correlation of the two temporal modes; the intrapulse correlation gives an exact zero contribution, as detailed in Appendix B. In this sense, an EPR variance below 2 is due to ponderomotive squeezing between the early and late modes.

B. Comparison with numerical results

Reference [16] provides a procedure to express analytically (in integral form) the covariance matrix of arbitrary temporal modes of the continuous steady-state output field of an optomechanical cavity. Arbitrary parameter regimes (e.g., nonzero detuning, sideband resolving cavity, strong coupling, etc.) can be studied numerically this way, as long as the system is stable and reaches a steady state. The form of the mode functions defined in Eqs. (23), for vanishing T_{sep} , allows one to compute symbolically the *exact* expression of the covariance matrix, and the EPR variance is readily obtained from the entries of the latter. The exact (symbolic) formula for the EPR variance is cumbersome and not very informative in its symbolic form, but it provides (exact) numerical results upon evaluation with fixed parameters; in this section numerical results refer to the evaluation of the exact symbolic expression with numerical values. We compare below the approximate formula, Eq. (24), to this approximation-free method.

In the following, unless otherwise stated, we assume $\omega_m/2\pi = 1$ MHz, $\kappa = 10\omega_m$, $Q = \omega_m/\gamma_m = 10^8$, and $n_{\text{th}} = 10^4$. This parameter set is partly inspired by a recent experiment [22]. All plots refer to the case $\eta = 1$ and $T_{\text{sep}} = 0$ (which corresponds to the limit where T_{sep} does not significantly alter Δ_{EPR}). The optimal angle ϕ_{opt} for the exact EPR variance is found analytically and used throughout all figures. The scripts and data for generating the plots are freely available online [54].

Figure 4 shows the minimal EPR variance versus optomechanical coupling g (and quantum cooperativity \mathcal{C}_q), comparing the approximate formula, Eq. (27) (red line), to the exact results (green circles) of the approximation-free symbolic expression. In the latter, for each g , we sweep over Γ to determine the minimal value of Δ_{EPR} . For cooperativities $\mathcal{C}_q \gtrsim 3$ the plots overlap well. In particular, the exact result confirms the surprising presence of entanglement at small cooperativities. The approximate formula becomes inaccurate




FIG. 4. Approximate minimal EPR variance from Eq. (27) (red solid line), exact EPR variance (green circles) and optimal entanglement witness (blue dots) versus optomechanical coupling g (lower x axis) and quantum cooperativity C_q (upper x axis). Threshold for separable states is at 2 (solid black line), the yellow shaded area represents the region of entanglement for the EPR variance and the optimal witness. This applies to all other figures.

at larger cooperativities because the restriction on the pulse bandwidths, Eq. (25) for $\Gamma = \Gamma_{\text{opt}}$, does not hold any more: In Fig. 4, the approximate Δ_{EPR} predicted by the red curve departs from the exact results given by the green circles. The exact Δ_{EPR} rises above the separability threshold 2 when the cooperativity increases because the EPR-variance criterion is not necessary for entanglement and fails to detect that certain states are entangled. For every two-mode Gaussian state (the class of states the temporal modes of the light belong to, recall Sec. III B) it is possible to find the *optimal* entanglement witness, based on linear combinations of second moments (covariances), that decides whether the state is entangled or not [49,55]. Because the EPR variance is a (in general suboptimal) witness based on second moments as well, we can plot the optimal witness on the same y -axis with the same separability thresholds at 2. The blue dots in Fig. 4 are the optimal-witness values of the states computed exactly. They monotonically decrease as C_q increases, therefore confirming the expected behavior that larger coherent coupling does not worsen the detection of entanglement. Interestingly, the approximate formula for the EPR variance and the optimal witness overlap well. We interpret this to be a result of the general scaling of squeezing as $1/C_q$ in the limit of large cooperativity.

Figure 5 shows how the EPR-variance changes with the pulse bandwidths Γ according to the approximate formula, Eq. (24) (solid lines), and compared to the exact results (circles). All curves display a single global minimum that is not a sharp feature. Thus the optimization over the pulse bandwidths is not too difficult in principle; especially in an experimental scenario where all the parameters are not known exactly. According to formula (24), larger pulse bandwidths will always yield some entanglement though one has to keep in mind the restriction of Eq. (25) that limits the validity of the




FIG. 5. Approximate minimal EPR variance from Eq. (27) (solid lines), exact EPR variance (circles), optimal entanglement witness (dots) versus pulse bandwidth Γ for cooperativities of $C_q = 0.1, 1, 10$ in red, green, and blue, respectively.

formula with respect to large Γ . As mentioned in the previous section, thermal noise on the mechanics is the sole decoherence channel of our model, and therefore pulses decaying faster than the thermal decoherence time $1/\Gamma_{\text{th}}$ will display some coherence. In practice, broadband pulses (short in time) will resolve other incoherent spectral components (electronic filters, additional mechanical modes, etc.) not accounted for in the present model. Close to the minima, we see good agreement for $C_q \lesssim 1$, consistently with Fig. 4. The exact EPR variance attains larger values at larger cooperativity because it is a suboptimal witness, as in Fig. 4. On the curve $C_q = 1$, the approximate formula and the exact results agree across the minimum and no more at larger bandwidths where the restriction of Eq. (25) does not hold.

In Fig. 6 we illustrate the dependence of the minimal EPR variance and the optimal witness on the temperature of the mechanical oscillator's bath, parametrized by its mean thermal occupation n_{th} . The cooperativity increases like the inverse of n_{th} . The approximate formula, Eq. (27) (red line), and the exact numerical result (green circles) agree when $C_q > 1$. The exact Δ_{EPR} and the optimized witness appear to saturate at a minimal value of 50% of squeezing below shot noise, just like the approximate formula predicts. Formula (24) becomes inaccurate as n_{th} grows large where, again, the restriction of Eq. (25) does not hold any more. At large temperature of the mechanical bath, the optimal witness (blue dots) predicts retrievable entanglement, which is similar to the behavior at small coupling on Fig. 4.

In realistic experiments, zero detuning is a challenging regime of operation because it is at the border to the unstable regime of the optomechanical dynamics at blue detunings. Therefore, in practice, the laser drive is usually slightly red detuned from the cavity resonance. In Fig. 7 we study the effects of detuning on the minimal EPR variance with the exact expressions of the covariance matrix: The circles correspond to the exact Δ_{EPR} and the dots to the optimal-witness values. For comparison, the values of formula Eq. (27) (only




FIG. 6. Approximate minimal EPR variance from Eq. (27) (red solid line), exact EPR variance (green circles), and optimal entanglement witness (blue dots) versus mechanical bath temperature, parametrized in terms of the mean thermal occupation number, for fixed optomechanical coupling $g/2\pi = 15.8$ kHz.

valid for zero detuning) are displayed as dashed lines. As the detuning approaches the cavity linewidth κ the separability bound violation diminishes because the strength of the sidebands’ spectral components in the cavity output field is reduced by the cavity profile. This is analogous to decreasing the detection efficiency (passive losses), in the sense that the spectral weight of the signal extracted by the mode functions decreases relative to the shot noise component. On the other hand, detuning does not introduce any additional noise, therefore the EPR variance does not increase above 2. In Figs. 4 and 5, where the detuning was zero, the exact EPR




FIG. 7. Exact EPR variance (circles) and optimal entanglement witness (dots) versus red detuning of the driving field from cavity resonance. The optomechanical coupling is kept constant corresponding to a quantum cooperativity of $C_q = 0.1, 1, 10$ for red, green, and blue symbols, respectively. The dashed lines are the approximate minimal EPR-variance formula, Eq. (27), valid only at $\delta = 0$ (displayed for comparison).

variance increases with cooperativity and Fig. 7 shows this too for large cooperativities and small detunings. Remarkably, at large cooperativity, some detuning reduces the minimal EPR variance down to an asymptotic value close to the prediction of the approximate formula Eq. (27) for zero detuning.

C. Remarks on shot-noise levels and multimode entanglement

In this section, we comment on the—somewhat subtle—role of shot noise levels in experimental entanglement detection in optomechanical systems. Given the canonical coordinates $O = (x_L, p_L, x_E, p_E)$, one can capture the second moments in a 4×4 covariance matrix Ξ with entries

$$\Xi_{i,j} := \langle O_i O_j + O_j O_i \rangle, \tag{29}$$

for vanishing means or first moments $\langle O_j \rangle$ for $j = 1, \dots, 4$. Any covariance matrix of a quantum state satisfies the Heisenberg uncertainty principle [40–42],

$$\Xi + i\sigma \geq 0, \tag{30}$$

where σ is the symplectic matrix incorporating the canonical commutation relations.

We will now turn to entanglement criteria. Any entanglement test linear in Ξ can be written in the form

$$\text{tr}(X\Xi) < 1, \tag{31}$$

where X is the 4×4 matrix that captures the measurement settings. It takes a moment of thought—and is explained in Ref. [49]—that the Duan criterion

$$\Delta_{\text{EPR}} = \text{tr}(X\Xi) \tag{32}$$

of Ref. [47] corresponds to a specific such choice for X . Such tests are not only convenient for their simplicity in experimental implementations: Their linear nature in Ξ renders the assessment of confidence regions of tests simple and feasible.

There is a subtle aspect that one needs to keep in mind when experimentally verifying entanglement: For a bipartite Gaussian state, a state being entangled and having a positive partial transpose is one to one. That is, exactly the covariance matrices of separable Gaussian quantum states will correspond to covariance matrices that satisfy

$$\Xi^\Gamma + i\sigma \geq 0, \tag{33}$$

where Ξ^Γ is the covariance matrix of the partial transpose. A slightly inaccurate experimental assessment of the shot noise level will correspond to a matrix $x\sigma$ where the real x is slightly different from unity. That means that when in such a picture the matrix Ξ is slightly unphysical,

$$\Xi + ix\sigma \not\geq 0, \tag{34}$$

it seemingly comes along with the Gaussian state being certified as being entangled

$$\Xi^\Gamma + ix\sigma \not\geq 0, \tag{35}$$

even if it is not. Therefore, to certify entanglement with confidence it is crucial to obtain a precise shot noise characterization, taking into account statistical fluctuations and any temporal drift. Note that these effects can be highly relevant even if the states involved are close to pure. In other words, if covariance matrices recovered are close to being pure [and

hence close to the boundary of the convex set of covariance matrices defined by Eq. (33)], then enormous care is necessary when drawing the conclusion that the state is entangled: This may be an artifact of an insufficiently calibrated shot noise level.

This issue is aggravated in the multimode case, which is specifically interesting when assessing entanglement between several optical and mechanical modes. Entanglement tests still take the form of Eq. (31), now Ξ being a symmetric $2n \times 2n$ matrix for n modes in total [49]. Such tests are highly convenient for detecting multimode entanglement in optomechanical systems, in that the optimal test for an anticipated quantum state can be efficiently found by means of methods of semidefinite programming [49], so convex optimization techniques [56].

The above-mentioned situation is now expected to be generic: In common experiments, some modes of local subsystems will be close to being pure. A more sophisticated statement of this kind is that in similar ways as natural quantum states are close to being low-rank states [57], commonly encountered covariance matrices Ξ will have a low quantity r that can be seen as a “symplectic rank”: If m is the number of unit eigenvalues of $-(\Xi\sigma)^2$, then

$$r = n - m. \quad (36)$$

A pure Gaussian state will have $r = 0$, a state each mode of which is mixed $r = n$. In this language, commonly encountered Gaussian states will feature covariance matrices that are well approximated by covariance matrices that have a value of r different from n : Some modes will be very susceptible to inaccurately estimated shot noise levels. If they are slightly underestimated, then most naturally encountered states will seem entangled, even if there is no entanglement in the system. This is an important observation little appreciated so far in the literature. This observation also comes hand in hand with the fact that in practical recoveries, a slight unphysicality of the covariance matrices goes hand in hand with entanglement being detected. Having said that, this applies only to the situation of inaccurately assessed shot noise levels: in some setting, even a weak signal in optomechanical systems subjected to very high noise levels can lead to strongly significant predictions [58]. Again, this is an aspect one has to be very careful about when assessing optomechanical entanglement.

V. CONCLUSION

In this work, we have presented an argument to demonstrate the presence of stationary optomechanical entanglement in a continuously driven optomechanical cavity. The argument relies on the extraction of temporally ordered modes from the continuous photocurrent of homodyne detection in postprocessing—no modulation of the drive is needed. The analytic study of a specific scheme shows that EPR squeezing can reach up to 50% below the threshold of separable states for large quantum cooperativity C_q . Our approximate formula for the EPR variance predicts that this limit is approached as C_q^{-1} . Remarkably, this limit seems to hold also for the exact EPR variance as well as for optimal entanglement

witnesses which are linear in the second moments. It would be interesting to establish this as a strict limit.

We have studied a specific class of variational mode profiles, which are physically well motivated, and are theoretically capable to reveal entanglement. Nevertheless, a systematic optimization of the mode functions would be desirable. This could be based, e.g., on the approach indicated in the end of Appendix B 2.

The single-mode model of the mechanical oscillator has been sufficient to fully develop our entanglement verification argument. Now, single-mode resonators are rare and it turns out that our scheme can be generalized to multiple mechanical modes: for each modes an early and late pair of mode operators, Eq. (17), are defined such that the covariance matrix, of dimension twice the number of modes included, can be computed. Entanglement in this state can be assessed with respect to the bipartition early-late. The inclusion of more modes improves the purity of the reconstructed state, in the sense that spectral contributions from the included modes are treated as signal rather than strong noise. This procedure (original and detailed study in Ref. [53]) might significantly improve experimental attempts, together with the considerations on physical states reconstruction of Sec. IV C.

We hope that our scheme provides a viable pathway to demonstrate stationary optomechanical entanglement, as predicted over a decade ago [16]. It would open a way for sophisticated protocols providing a full characterization of the optomechanical entanglement from, e.g., state tomography. We think that a successful implementation of our scheme would constitute a textbook experiment exploring the Heisenberg–von Neumann cut between measured system and measurement apparatus in the example of an optomechanical position meter.

ACKNOWLEDGMENTS

The authors are very thankful to Claus Gärtner and Marek Gluza for important discussions and inputs in the course of this project. C.G. acknowledges support from the European Union’s Horizon 2020 research and innovation program under the Marie Skłodowska-Curie Grant No. 722923 (OMT). N.W. acknowledges funding support from the European Unions Horizon 2020 research and innovation programme under the Marie Skłodowska-Curie Grant No. 750905. J.E. acknowledges support by the DFG (CRC183, FOR 2724) and the FQXi. M.A. acknowledges support by the European Research Council (ERC QLev4G). This project was supported by the doctoral school CoQuS (Project No. W1210). K.H. acknowledges support through DFG through CRC 1227 DQ-mat Project No. A06 and Germany’s Excellence Strategy – EXC-2123 QuantumFrontiers – 390837967.

APPENDIX A: LIGHT-LIGHT ENTANGLEMENT IMPLIES LIGHT-MECHANICS ENTANGLEMENT

In this Appendix we provide the details of the indirect proof of entanglement in the scenario shown in Fig. 1. The initial state is a product state of E, M, and L,

$$\rho_{\text{EML}}^{\text{init}} = \rho_E \otimes \rho_M \otimes \rho_L. \quad (\text{A1})$$

The first quantum channel \mathcal{E}_{EM} acts nontrivially on E and M only. If this quantum channel does *not* generate entanglement between E and M, then

$$\begin{aligned} (\mathcal{E}_{EM} \otimes \mathbb{1}_L) \rho_{EML}^{\text{init}} &= \mathcal{E}_{EM}(\rho_E \otimes \rho_M) \otimes \rho_L \\ &= \sum_i p_i \rho_E^i \otimes \rho_M^i \otimes \rho_L. \end{aligned} \quad (\text{A2})$$

In this case, any subsequent channel acting on M and L cannot generate entanglement between E and L: The final state is

$$\begin{aligned} \rho_{EML}^{\text{fin}} &= (\mathbb{1}_L \otimes \mathcal{E}_{ML})(\mathcal{E}_{EM} \otimes \mathbb{1}_L) \rho_{EML}^{\text{init}} \\ &= \sum_i p_i \rho_E^i \otimes \mathcal{E}_{ML}(\rho_M^i \otimes \rho_L) \end{aligned} \quad (\text{A3})$$

and the reduced state of E and L is

$$\rho_{EL}^{\text{fin}} = \text{tr}_M[\rho_{EML}^{\text{fin}}] = \sum_i p_i \rho_E^i \otimes \tilde{\rho}_L^i, \quad (\text{A4})$$

where $\tilde{\rho}_L^i = \text{tr}_M[\mathcal{E}_{ML}(\rho_M^i \otimes \rho_L)]$. The state ρ_{EL}^{fin} is separable. In essence, this statement is equivalent to the obvious fact that entanglement cannot be generated by local operations. In Sec. III A we use the contraposited statement: If ρ_{EL}^{fin} is entangled, then \mathcal{E}_{EM} must have created E-M entanglement.

In the literature we find that, with the same pairwise interaction sequence, it is possible to distribute entanglement between parties E and L via a mediator M, in such a way that M is never entangled with E and/or L [35–39]. There, the initial state of E, M, and L is a separable state but it crucially *is* classically correlated. It is because we require that the initial state is uncorrelated that we can write in general that the action of \mathcal{E}_{EM} yields a separable state in Eq. (A2).

APPENDIX B: DERIVATION OF ANALYTICAL FORMULA FOR THE EPR VARIANCE

This section presents the derivation of formula Eq. (24) for the EPR variance for the exponentially decaying mode functions defined in Eqs. (23), valid in the regime $\kappa \gg \omega_m \gg \gamma_m$, $\Gamma \ll \omega_m/\sqrt{n_{\text{th}}(C+1)}$ and $\delta = 0$. The methodology below is strongly inspired from Ref. [16].

1. Solution of the Langevin equations in Fourier space

In this document, the definition of the Fourier transform of a function or operator h is

$$\mathcal{F}[h(t)]_\omega := \int_{-\infty}^{\infty} \frac{dt}{\sqrt{2\pi}} e^{i\omega t} h(t) = h(\omega), \quad (\text{B1a})$$

$$\mathcal{F}^{-1}[h(\omega)]_t := \int_{-\infty}^{\infty} \frac{d\omega}{\sqrt{2\pi}} e^{-i\omega t} h(\omega) = h(t). \quad (\text{B1b})$$

In the operator context we define that the the adjunction is performed after the Fourier transformation: We write

$$h^\dagger(\omega) := (h(\omega))^\dagger := (\mathcal{F}[h]_\omega)^\dagger = \mathcal{F}[h^\dagger]_{-\omega}. \quad (\text{B2})$$

The Fourier transform of the QLE, Eqs. (6), with $\delta = 0$, are

$$-i\omega x_m(\omega) = \omega_m p_m(\omega), \quad (\text{B3a})$$

$$\begin{aligned} -i\omega p_m(\omega) &= -\gamma_m p_m(\omega) - \omega_m x_m(\omega) \\ &\quad - 2gx_c(\omega) + \sqrt{2\gamma_m} \xi(\omega), \end{aligned} \quad (\text{B3b})$$

$$-i\omega x_c(\omega) = -\frac{\kappa}{2} x_c(\omega) + \sqrt{\kappa} x_{\text{in}}(\omega), \quad (\text{B3c})$$

$$\begin{aligned} -i\omega p_c(\omega) &= -\frac{\kappa}{2} p_c(\omega) - 2gx_m(\omega) \\ &\quad + \sqrt{\kappa} p_{\text{in}}(\omega). \end{aligned} \quad (\text{B3d})$$

We express x_c and p_c in terms of the driving noises: electromagnetic vacuum fluctuations (shot noise) x_{in} , p_{in} and Hermitian thermal mechanical noise ξ . With the input-output relations, $x_{\text{out}} = \sqrt{\kappa} x_c - x_{\text{in}}$ (analogously for p_{out}) [34], we find the quadratures of the light escaping the cavity, Eqs. (7),

$$\begin{aligned} x_{\text{out}}(\omega) &= \mathcal{S}(\omega) x_{\text{in}}(\omega), \\ p_{\text{out}}(\omega) &= \mathcal{S}(\omega) p_{\text{in}}(\omega) + 4g^2 \chi_{\text{opt}}^2(\omega) \chi_m(\omega) x_{\text{in}}(\omega) \\ &\quad - 2g \chi_{\text{opt}}(\omega) \chi_m(\omega) \sqrt{2\gamma_m} \xi(\omega). \end{aligned}$$

It will be convenient to use the following abbreviations for the prefactors of shot noise, back-action noise, and thermal noise, respectively:

$$\mathcal{S}(\omega) := \frac{\frac{\kappa}{2} + i\omega}{\frac{\kappa}{2} - i\omega}, \quad (\text{B4a})$$

$$\mathcal{B}(\omega) := 2g^2 \chi_{\text{opt}}^2(\omega) \chi_m(\omega), \quad (\text{B4b})$$

$$\mathcal{T}(\omega) := 2g \sqrt{\gamma_m(n_{\text{th}} + 1/2)} \chi_{\text{opt}}(\omega) \chi_m(\omega). \quad (\text{B4c})$$

These functions obey $\mathcal{S}^*(\omega) = \mathcal{S}(-\omega)$ and similarly for $\mathcal{B}(\omega)$ and $\mathcal{T}(\omega)$. The optical and mechanical susceptibilities were introduced in Eqs. (9) and (8), respectively.

We find that the annihilation operators of the output light field in Fourier space is

$$\begin{aligned} a_{\text{out}}(\omega) &= \frac{x_c^{\text{out}}(\omega) + ip_c^{\text{out}}(\omega)}{\sqrt{2}} \\ &= \mathcal{S}(\omega) a_{\text{in}}(\omega) - \frac{i\mathcal{T}(\omega)}{\sqrt{n_{\text{th}} + 1/2}} \xi(\omega) \\ &\quad + i\mathcal{B}(\omega) [a_{\text{in}}(\omega) + a_{\text{in}}^\dagger(-\omega)] \end{aligned} \quad (\text{B5})$$

and $a_{\text{out}}^\dagger(\omega) := [a_{\text{out}}(\omega)]^\dagger$. We used the relations between quadratures and ladder operators, Eq. (2), in Fourier space.

2. Exact formula for the EPR variance

The mode operators, defined in Eq. (17), become a convolution in frequency domain

$$r_i = \int_{-\infty}^{\infty} d\omega f_i(-\omega) a_{\text{out}}(\omega) \quad (\text{B6})$$

as a consequence of Plancherel's theorem.

Four different correlators appear in the expression of the EPR variance in terms of ladder operators, Eq. (22): $\langle r_j^\dagger r_j \rangle$, $\langle r_j r_j^\dagger \rangle$, $\langle r_j^\dagger r_k^\dagger \rangle$, and $\langle r_j r_k \rangle$; with $j, k = E, L$ and $k \neq j$. We write them as frequency integrals using Eq. (B6)

$$\begin{aligned} \langle r_j^{(\dagger)} r_k^{(\dagger)} \rangle &= \iint_{-\infty}^{\infty} d\omega d\omega' f_j^{(*)}(-\omega) f_k^{(*)}(-\omega') \\ &\quad \times \langle a_{\text{out}}^{(\dagger)}(\omega) a_{\text{out}}^{(\dagger)}(\omega') \rangle, \end{aligned} \quad (\text{B7})$$

where the superscripts (\dagger) and $(*)$ indicate presence or absence of Hermitian and complex conjugation, respectively.

One keeps track of the factor $e^{i\phi}$ in Eq. (22) with the following replacement convention $f_L(\omega) \rightarrow f_L(\omega)e^{i\phi}$.

We find the expressions of the four correlators above from Eq. (B7) using Eq. (B5), the Markovian bath's correlators Eqs. (5) and (4) in frequency space, and the shorthand

$$\begin{aligned} \Delta_{\text{EPR}} = & \sum_{j=\text{E,L}} \left\{ \int_{-\infty}^{\infty} d\omega f_j(\omega) f_j^*(\omega) \left[\frac{1}{2} \mathcal{S}(\omega) \mathcal{S}(-\omega) + \mathcal{B}(\omega) \mathcal{B}(-\omega) + \mathcal{T}(\omega) \mathcal{T}(-\omega) \right] + \text{c.c.} \right\} \\ & - \sum_{\substack{j,k=\text{E,L} \\ k \neq j}} \left\{ \int_{-\infty}^{\infty} d\omega f_j(-\omega) f_k(\omega) [\mathcal{B}(\omega) \mathcal{B}(-\omega) + \mathcal{T}(\omega) \mathcal{T}(-\omega)] + \text{c.c.} \right\} \\ & + \sum_{j=\text{E,L}} \left[\int_{-\infty}^{\infty} d\omega f_j(\omega) f_j^*(\omega) i \mathcal{S}(-\omega) \mathcal{B}(\omega) + \text{c.c.} \right] \\ & + \sum_{\substack{j,k=\text{E,L} \\ k \neq j}} \left[\int_{-\infty}^{\infty} d\omega f_j(-\omega) f_k(\omega) i \mathcal{S}(-\omega) \mathcal{B}(\omega) + \text{c.c.} \right]. \end{aligned} \quad (\text{B8})$$

This relation is exact if the drive is not detuned with respect to the cavity. It also reveals how the driving noises couple to each other and to the mode functions: $\mathcal{S}(\omega)\mathcal{S}(-\omega)$, $\mathcal{B}(\omega)\mathcal{B}(-\omega)$, and $\mathcal{T}(\omega)\mathcal{T}(-\omega)$ come from the autocorrelations of the noises, while $\mathcal{S}(-\omega)\mathcal{B}(\omega)$ comes from the correlation between shot noise and back-action noise. The correlators are overlapped either with $f_j f_j^*$ (we call them *intramode* integrals) or with $f_j f_k$ (we call them *intermode* integrals).

So far, we did not use that f_E and f_L are time ordered and nonoverlapping, therefore Eq. (B8) is valid for arbitrary mode functions satisfying the orthonormality constraint, Eq. (18). Moreover, Eq. (B8) takes a compact matrix form. Indeed, notice that $\mathcal{S}(\omega)\mathcal{S}(-\omega) = 1$, and call

$$\begin{aligned} D(\omega) &:= \mathcal{B}(\omega)\mathcal{B}(-\omega) + \mathcal{T}(\omega)\mathcal{T}(-\omega) \\ &= 4g^2 |\chi_{\text{opt}}(\omega)|^2 |\chi_m(\omega)|^2 [g^2 |\chi_{\text{opt}}(\omega)|^2 \\ &\quad + \gamma_m(n_{\text{th}} + 1/2)], \end{aligned} \quad (\text{B9a})$$

$$\begin{aligned} P(\omega) &:= \mathcal{S}(-\omega)\mathcal{B}(\omega) \\ &= 2g^2 \mathcal{S}(-\omega) \chi_{\text{opt}}^2(\omega) \chi_m(\omega), \end{aligned} \quad (\text{B9b})$$

with $D^*(\omega) = D(-\omega) = D(\omega)$ (i.e., real) and $P^*(\omega) = P(-\omega)$. On expanding the sums in Eq. (B8), making sure the argument of f_L is $-\omega$, one obtains the compact matrix expression

$$\Delta_{\text{EPR}} = 2 + \int_{-\infty}^{\infty} d\omega v^\dagger(\omega) M(\omega) v(\omega), \quad (\text{B10})$$

where $v(\omega) := (f_E(\omega), f_L^*(-\omega), f_E^*(\omega), f_L(-\omega))^T$. The matrix M is Hermitian as

$$M := \begin{pmatrix} D - P_I & -D - iP_R & 0 & 0 \\ -D + iP_R & D + P_I & 0 & 0 \\ 0 & 0 & D - P_I & -D + iP_R \\ 0 & 0 & -D - iP_R & D + P_I \end{pmatrix} \quad (\text{B11})$$

with $P_R := \text{Re}[P]$ and $P_I := \text{Im}[P]$ being the real and imaginary parts of P , respectively.

notations and symmetries of Eqs. (B4). The thermal noise integrals need to be combined appropriately to take the form of Eqs. (5) (in frequency space). Each correlator at this point is a single frequency integral and the EPR variance, Eq. (22), can be written as the following explicitly real expression

It is interesting to look at the problem of minimizing Eq. (B10) under the constraints that the mode functions are time-ordered—necessary to infer optomechanical entanglement based on light modes entanglement—and orthonormal, Eq. (18). Titchmarsh's theorem [59,60] states that the causality constraint is equivalent to mode functions determined by their real parts only. Therefore, the constraints can be formulated in a quadratic form such that the quadratic minimization problem can be solved in polynomial times with linear programming methods, according to Ref. [61]. We were not successful with a simple and naive approach to perform the minimization this way. We attempted to solve it as an eigenvalue problem but were not successful either: the main issues were the wide parameter spread (ratio between largest and smallest scale is 10^8) and the form of the normalization constraint. Moreover, optimizing the mode functions to minimize Δ_{EPR} is suboptimal but we expect that repeating our analysis for Duan's criterion [47] in its actual form or even a general witness that is linear in covariance matrices [49] is a simple generalization.

3. Approximate formula for the EPR variance

Under the assumption that $\kappa \gg \omega_m \gg \gamma_m$ motivated in Sec. III C, we made the approximations of Eqs. (11). We update the noise prefactors of Eqs. (B4) accordingly

$$\mathcal{S}(\omega) \approx 1, \quad (\text{B12a})$$

$$\mathcal{B}(\omega) \approx 2\Gamma_{\text{ro}} \chi_m(\omega), \quad (\text{B12b})$$

$$\mathcal{T}(\omega) \approx 2\sqrt{\Gamma_{\text{ro}} \Gamma_{\text{th}}} \chi_m(\omega), \quad (\text{B12c})$$

such that $\mathcal{S}^* = \mathcal{S}$, $\mathcal{B}^*(\omega) = \mathcal{B}(-\omega)$, and $\mathcal{T}^*(\omega) = \mathcal{T}(-\omega)$. We defined Γ_{ro} and Γ_{th} in Eqs. (13) and (15), respectively. These approximations simplify the terms in the curly brackets in Eq. (B8): The remaining ω dependence is $|\chi_m|^2$ or χ_m .

The mode functions of Eqs. (23) are Lorentzians in frequency space,

$$f_{\text{E/L}}(\omega) = N_{\text{E/L}} \frac{e^{\mp i\omega T_{\text{sep}}/2}}{\omega - \omega_{\text{E/L}}}, \quad (\text{B13})$$

with $\omega_{E/L} := \mp(\omega_m + i\Gamma)$ (minus signs associated to index E) and

$$N_{E/L} = \mp i \sqrt{\frac{\Gamma}{\pi}} e^{i\omega_m T_{\text{sep}}/2} \quad (\text{B14})$$

is the normalization factor.

The integrands in Eq. (B8) are thus products of the mode functions, Eq. (B13), with the mechanical susceptibility, Eq. (11a), or its modulus square, Eq. (11b). Terms like $(\omega - \omega_E)^{-1}(\omega - \omega_-)^{-1}$ and $(\omega - \omega_L)^{-1}(\omega - \omega_+)^{-1}$ are resonant and the next largest terms scale relatively like $O[\Gamma\sqrt{n_{\text{th}}}(C_q + 1)/\omega_m]$. As a further (purely technical) simplification we keep only the resonant terms and require that $\Gamma \ll \omega_m/\sqrt{n_{\text{th}}}(C + 1)$; this is the origin of Eq. (25). The thus approximated four integrals of Eq. (B8) can be evaluated with the residue theorem, we find [keeping the line structure of Eq. (B8)]

$$\begin{aligned} \Delta_{\text{EPR}} = & 2 + 8(\Gamma_{\text{ro}} + \Gamma_{\text{th}}) \frac{1}{\gamma_m(\Gamma + \frac{\gamma_m}{2})} \\ & - 8(\Gamma_{\text{ro}} + \Gamma_{\text{th}}) \frac{\Gamma e^{-\gamma_m T_{\text{sep}}/2}}{\gamma_m(\Gamma + \frac{\gamma_m}{2})^2} \cos \phi + 0 \\ & - 4\Gamma_{\text{ro}} \frac{\Gamma e^{-\gamma_m T_{\text{sep}}/2}}{(\Gamma + \frac{\gamma_m}{2})^2} \cos \phi. \end{aligned} \quad (\text{B15})$$

This concludes the derivation of the approximate formula of the EPR variance, for ideal detection ($\eta = 1$), in the regime $\kappa \gg \omega_m \gg \gamma_m$, $\Gamma \ll \omega_m/\sqrt{n_{\text{th}}}(C + 1)$ and $\delta = 0$. It is Eq. (24) evaluated at $\eta = 1$ (called $\Delta_{\text{EPR}}|_{\eta=1}$ below).

Finally, we model inefficient detection (passive losses) by a beam-splitter of transitivity η right before an ideal (efficiency 1) detector. In the detected channel the field operator is

$$a_{\text{out}}^{\text{meas}} = \sqrt{\eta} a_{\text{out}} + \sqrt{1 - \eta} a_{\text{shot}} \quad (\text{B16})$$

in which a_{out} is the cavity output operator as in Eq. (B5), and a_{shot} is the operator of shot noise that entered the free port of the beam-splitter. The correlators appearing in Δ_{EPR} , Eq. (B7), factorize because a_{out} and a_{shot} are uncorrelated. Using that the intrapulse autocorrelators of shot noise equals 2, we find that the EPR variance accounting for detection inefficiency, Eq. (24), is given by

$$\Delta_{\text{EPR}} = \eta \Delta_{\text{EPR}}|_{\eta=1} + (1 - \eta)2. \quad (\text{B17})$$

We have denoted here with $\Delta_{\text{EPR}}|_{\eta=1}$ the expression for the EPR variance for unit detection efficiency derived in this Appendix, Eq. (B15).

-
- [1] J. D. Teufel, T. Donner, D. Li, J. W. Harlow, M. S. Allman, K. Cicak, A. J. Sirois, J. D. Whittaker, K. W. Lehnert, and R. W. Simmonds, *Nature* **475**, 359 (2011).
- [2] J. Chan, T. Alegre, A. Safavi-Naeini, J. Hill, A. Krause, S. Groeblacher, M. Aspelmeyer, and O. Painter, *Nature* **478**, 89 (2011).
- [3] D. W. C. Brooks, T. Botter, S. Schreppler, T. P. Purdy, N. Brahms, and D. M. Stamper-Kurn, *Nature* **488**, 476 (2012).
- [4] A. H. Safavi-Naeini, S. Gröblacher, J. T. Hill, J. Chan, M. Aspelmeyer, and O. Painter, *Nature* **500**, 185 (2013).
- [5] T. P. Purdy, P.-L. Yu, R. W. Peterson, N. S. Kampel, and C. A. Regal, *Phys. Rev. X* **3**, 031012 (2013).
- [6] S. Barzanjeh, E. S. Redchenko, E. S. Redchenko, M. Peruzzo, M. Wulf, D. P. Lewis, G. Arnold, and J. M. Fink, *Nature* **570**, 480 (2019).
- [7] J. Chen, M. Rossi, D. Mason, and A. Schliesser, *Nat. Commun.* **11**, 943 (2020).
- [8] C. F. Ockeloen-Korppi, E. Damskäg, J.-M. Pirkkalainen, M. Asjad, A. A. Clerk, F. Massel, M. J. Woolley, and M. A. Sillanpää, *Nature* **556**, 478 (2018).
- [9] R. Riedinger, A. Wallucks, I. Marinković, C. Löschnauer, M. Aspelmeyer, S. Hong, and S. Gröblacher, *Nature* **556**, 473 (2018).
- [10] T. P. Purdy, R. W. Peterson, and C. A. Regal, *Science* **339**, 801 (2013).
- [11] C. U. Lei, A. J. Weinstein, J. Suh, E. E. Wollman, A. Kronwald, F. Marquardt, A. A. Clerk, and K. C. Schwab, *Phys. Rev. Lett.* **117**, 100801 (2016).
- [12] J. B. Clark, F. Lecocq, R. W. Simmonds, J. Aumentado, and J. D. Teufel, *Nature* **541**, 191 (2017).
- [13] I. Shomroni, L. Qiu, D. Malz, A. Nunnenkamp, and T. J. Kippenberg, *Nat. Comm.* **10**, 2086 (2019).
- [14] T. A. Palomaki, J. D. Teufel, R. W. Simmonds, and K. W. Lehnert, *Science* **342**, 710 (2013).
- [15] I. Marinković, A. Wallucks, R. Riedinger, S. Hong, M. Aspelmeyer, and S. Gröblacher, *Phys. Rev. Lett.* **121**, 220404 (2018).
- [16] C. Genes, A. Mari, P. Tombesi, and D. Vitali, *Phys. Rev. A* **78**, 032316 (2008).
- [17] C. Genes, A. Mari, D. Vitali, and P. Tombesi, *Advances in Atomic Molecular and Optical Physics*, Vol. 57 (Academic Press, San Diego, CA, 2009), pp. 33–86.
- [18] S. G. Hofer, W. Wiczcerek, M. Aspelmeyer, and K. Hammerer, *Phys. Rev. A* **84**, 052327 (2011).
- [19] H. Miao, S. Danilishin, H. Müller-Ebhardt, and Y. Chen, *New J. Phys.* **12**, 083032 (2010).
- [20] H. Miao, S. Danilishin, H. Müller-Ebhardt, H. Rehbein, K. Somiya, and Y. Chen, *Phys. Rev. A* **81**, 012114 (2010).
- [21] S. Danilishin, H. Miao, H. Müller-Ebhardt, and Y. Chen, Optomechanical entanglement: How to prepare, verify and “steer” a macroscopic mechanical quantum state? *First International Workshop on Entangled Coherent States and Its Application to Quantum Information Science—Towards Macroscopic Quantum Communications, 26-28 November, 2012, Tokyo, Japan* (Tama-gawa University Quantum ICT Research Institute, 2012).
- [22] M. Rossi, D. Mason, J. Chen, and A. Schliesser, *Phys. Rev. Lett.* **123**, 163601 (2019).
- [23] H. Miao, S. Danilishin, and Y. Chen, *Phys. Rev. A* **81**, 052307 (2010).
- [24] J. von Neumann, *Mathematical Foundations of Quantum Mechanics* (Princeton University Press, Princeton, NJ, 1955).
- [25] W. Zurek, *Phys. Rev. D* **24**, 1516 (1981).
- [26] W. Zurek, *Rev. Mod. Phys.* **75**, 715 (2003).

- [27] M. Aspelmeyer, T. J. Kippenberg, and F. Marquardt, *Rev. Mod. Phys.* **86**, 1391 (2014).
- [28] P. Rabl, *Phys. Rev. Lett.* **107**, 063601 (2011).
- [29] A. Nunnenkamp, K. Børkje, and S. M. Girvin, *Phys. Rev. Lett.* **107**, 063602 (2011).
- [30] C. W. Gardiner and P. Zoller, *Quantum Noise*, 3rd ed. (Springer, Berlin, 2010).
- [31] A. Caldeira and A. Leggett, *Physica A* **121**, 587 (1983).
- [32] The QLE can be either expressed with the Brownian noise affecting the mechanical momentum quadrature only, as in Eqs. (6), or with the Brownian noise affecting both mechanical quadratures symmetrically. We performed the exact numerical computation based on the QLE with symmetric and asymmetric Brownian noise and we found that all the results presented in this work are the same in both cases up to a few parts per million.
- [33] The stability is most easily assessed by the Routh-Hurwitz criterion. Whenever the detuning is zero the dynamics is unconditionally stable [62].
- [34] C. W. Gardiner and M. J. Collett, *Phys. Rev. A* **31**, 3761 (1985).
- [35] T. S. Cubitt, F. Verstraete, W. Dür, and J. I. Cirac, *Phys. Rev. Lett.* **91**, 037902 (2003).
- [36] L. Mišta and N. Korolkova, *Phys. Rev. A* **77**, 050302(R) (2008).
- [37] A. Fedrizzi, M. Zuppardo, G. G. Gillett, M. A. Broome, M. P. Almeida, M. Paternostro, A. G. White, and T. Paterek, *Phys. Rev. Lett.* **111**, 230504 (2013).
- [38] C. Peuntinger, V. Chille, L. Mišta, N. Korolkova, M. Förtsch, J. Korger, C. Marquardt, and G. Leuchs, *Phys. Rev. Lett.* **111**, 230506 (2013).
- [39] C. E. Vollmer, D. Schulze, T. Eberle, V. Händchen, J. Fiurášek, and R. Schnabel, *Phys. Rev. Lett.* **111**, 230505 (2013).
- [40] J. Eisert and M. B. Plenio, *Int. J. Quant. Inf.* **1**, 479 (2003).
- [41] G. Adesso and F. Illuminati, *J. Phys. A* **40**, 7821 (2007).
- [42] C. Weedbrook, S. Pirandola, R. Garcia-Patron, N. J. Cerf, T. C. Ralph, J. H. Shapiro, and S. Lloyd, *Rev. Mod. Phys.* **84**, 621 (2012).
- [43] M. M. Wolf, G. Giedke, O. Krüger, R. F. Werner, and J. I. Cirac, *Phys. Rev. A* **69**, 052320 (2004).
- [44] G. Vidal and R. F. Werner, *Phys. Rev. A* **65**, 032314 (2002).
- [45] M. B. Plenio, *Phys. Rev. Lett.* **95**, 090503 (2005).
- [46] J. Eisert, Ph.D. thesis, University of Potsdam, 2001.
- [47] L.-M. Duan, G. Giedke, J. I. Cirac, and P. Zoller, *Phys. Rev. Lett.* **84**, 2722 (2000).
- [48] R. Simon, *Phys. Rev. Lett.* **84**, 2726 (2000).
- [49] P. Hyllus and J. Eisert, *New J. Phys.* **8**, 51 (2006).
- [50] J. Eisert, F. G. S. L. Brandao, and K. M. Audenaert, *New J. Phys.* **9**, 46 (2007).
- [51] K. M. R. Audenaert and M. B. Plenio, *New J. Phys.* **8**, 266 (2006).
- [52] O. Gühne, M. Reimpell, and R. F. Werner, *Phys. Rev. Lett.* **98**, 110502 (2007).
- [53] J. Hoelscher-Obermaier, Ph.D. thesis, University of Vienna, 2017.
- [54] C. Gut and K. Winkler (2019), doi: [10.5281/zenodo.3901001](https://doi.org/10.5281/zenodo.3901001).
- [55] Reference [49] provides a MATLAB function that computes the optimal witness given a covariance matrix.
- [56] S. Boyd and L. Vanderberghe, *Convex Optimization* (Cambridge University Press, Cambridge, 2004).
- [57] D. Gross, Y.-K. Liu, S. T. Flammia, S. Becker, and J. Eisert, *Phys. Rev. Lett.* **105**, 150401 (2010).
- [58] S. Groeblacher, A. Trubarov, N. Prigge, M. Aspelmeyer, and J. Eisert, *Nat. Comm.* **6**, 7606 (2015).
- [59] E. Titchmarsh, *Introduction to the Theory of Fourier Integrals* (Oxford University Press, Oxford, 1948).
- [60] H. Nussenzveig, *Causality and Dispersion Relations* (Elsevier/Academic Press, New York, 1972).
- [61] J. Park and S. Boyd, [arXiv:1703.07870](https://arxiv.org/abs/1703.07870) [math.OC].
- [62] S. G. Hofer, Ph.D. thesis, University of Vienna, 2015, http://othes.univie.ac.at/38975/1/2015-08-24_0217420.pdf.